

# **CBEI - Coordinating RTUs in Small & Medium Sized Commercial Buildings**



**Renewable Energy** 

2015 Building Technologies Office Peer Review





Jim Braun, jbraun@purdue.edu **CBEI/Purdue University** 

# **Project Summary**

### Timeline:

Start date: 5/1/2014 Planned end date: 4/30/2016

### Key Milestones

- 1. Adaptive control modeling, 10/15/14
- 2. Energy savings assessments, 2/28/15

### Budget:

Total DOE \$ to date: **\$350,000** Total future DOE \$: **\$200,000** 

### Target Market/Audience:

Small and medium-size commercial buildings (SMSCBs) served by RTUs

### Key Partners:

CBEI - Purdue

CBEI - Virginia Tech

Oak Ridge National Lab

Field Diagnostics Services, Inc.

FrontStreet Facilities Solution

### Project Goals:

- Develop, demonstrate, and evaluate an rooftop unit (RTU) coordinator that: a) minimizes energy consumption & peak demand; 2) does not require additional sensors; 3) requires minimal implementation expertise
- Further develop simulation tool that can be used as a testbed for evaluating control approaches in open spaces served by RTUs



Energy Efficiency & Renewable Energy



By 2030, deep energy retrofits that reduce energy use by 50% in existing SMSCB, which are less than 250,000 sq ft

#### Mission:

Develop, demonstrate and deploy technology systems and market pathways that permit early progress (20-30% energy use reductions) in Small and Medium Sized Commercial Buildings



CONSORTIUM for BUILDING ENERGY

INNOVATION



#### **Our Goals**:

- Enable deep energy retrofits in small to medium sized commercial buildings
- **Demonstrate energy efficient systems** tailored for SMSCBs in occupied buildings living labs
- Develop effective market pathways for energy efficiency with utilities and other commercial stakeholders: brokers, finance, service providers.
- Provide analytical tools to link state and local policies with utility efficiency programs





**Problem Statement**: Advanced controls for SMSCBs (small and medium-size commercial buildings) are rarely implemented because of poor overall economics. Low-touch, low-cost control implementations are needed.

### Target Market and Audience:

- Market is SMCBs that utilize RTUs for cooling.
- RTUs serve about 60% of commercial floor space & account for ~150 TWh of annual electrical usage (~1.56 Quads primary energy for cooling) & ~\$15B in electric bills.
- Audience is companies that can build successful businesses to deliver advanced RTU controls for SMSCBs.



## **Purpose and Objectives**


### Impact of Project:

- General algorithm to enable "Plug-and-Play" (PnP RTU) Coordinator → interface to thermostat; no additional measurements; adaptively learns behavior
- Variety of possible commercial implementations
  - cloud-based using web-enabled thermostats
  - low-cost RTU coordination control hardware
  - software overlay on top of existing (energy management system) EMS for enterprise solutions
  - implementation as a standard application within EMS
  - embedded in smart RTU controllers
- Demonstrating cost savings and different implementation approaches in collaboration with commercial partners
  - Energy savings potential of > 20 TWh electricity (~0.25 Quad primary) per year
  - Utility cost savings potential > \$2B per year
  - Minimal implementation costs once infrastructure is in place (e.g., communicating thermostats and cloud-based infrastructure or low-cost hardware/software for stand-alone setup at the site)

**Renewable Energy** 

# Approach – RTU Coordinator Algorithm

- Learns relationship between thermostat temperatures and RTU on/off staging (no other measurements required)
- Determines RTU staging to minimize energy (based on RTU rated power or measurements if available)






Energy Efficiency & Renewable Energy

# **Approach – RTU Coordinator Evaluation**

- Short-term field testing for controller evaluation & virtual testbed validation
- Virtual testbed simulation for 3-month comparison of controllers for identical weather and occupancy schedules: not possible at field sites


Central Baptist Church (CBC), Knoxville, TN





Harvest Grill (HG) Restaurant, Glenn Mills, PA






O thermostat ● supplysdiffue r

- RTU
- **HG Dining Area**: 4 RTUs, RTU1 has 2 stages with 3 times capacity and 35% greater efficiency than other RTUs
- CBC has 4, 2-stage identical RTUs



Energy Efficiency & Renewable Energy

## **Approach – Virtual Testbed**



# **Approach and Accomplishments**

**Key Issues**: 1) refining adaptive modeling approach for controller; 2) demonstrating cost savings potential; 3) developing alternative implementation approaches and demonstrating requirements


**Distinctive Characteristics**: 1) Energy efficient control with minimal sensors, set-up & infrastructure; 2) Unique simulation platform for assessing long-term RTU coordination control performance

### Summary of Accomplishments:

- Validation of virtual testbed at two sites
- Validation/demonstration of significant energy (e.g., 20%) and peak demand (e.g., 30%) savings
- Demonstration of alternative implementation platforms
- Developed relationships with commercial partners and customers for additional development and demonstration



## **Accomplishments - Short-Term Field Tests for CBC**



#### Conventional

- High peak demand
- Significant short cycling of equipment

#### Plug-n-Play (PnP)

- Utilizes RTU<sub>1</sub> and RTU<sub>3</sub> as much as possible; See T<sub>2</sub> and T<sub>4</sub> while corresponding RTUs are off.)
- Reduces short cycling with better comfort
- Significant peak demand reduction



# **Accomplishments – 1-Week Field Tests for CBC**

## **Energy and Demand Savings**

### **Comfort Comparisons**

	%EnergySavings8.23	Peak Demand Reduction (15 min moving average)
PnP	8.23	<u>42.57</u>

	Conv	PnP				
Max.						
Comfort	2.5°F	1.2°F				
violation						

### Notes

- Relatively small energy savings because units are identical → primary savings due to reduced cycling
- Large demand savings → units are oversized, zones served by RTUs are closely coupled, week test period doesn't contain the summer peaks
- Testing at field site limited to one week period with day-to-day alternating control approaches → need for longer term assessments



## **Accomplishments – Simulated Summer Results for CBC**


	June		Ju	ly	Aug	ust	3-Month Totals		
	Conv	PnP	Conv	PnP	Conv	PnP	Conv	PnP	
Energy (MWh)	5.9	5.5	7.8	7.1	5.5	4.8	19.2	17.4	
Energy Cost (\$)	588.3	546.5	780.0	714.0	553.1	475.8	1921.4	1736.3	
Peak Power (kW)	37.9	27.8	42.3	35.9	39.5	27.7	-	-	
Demand Charge (\$)	454.7	333.8	507.6	430.3	473.7	332.4	1435.9	1096.5	
Total Cost (\$)	1043.0	880.3	1287.6	1144.3	1026.8	808.2	3357.3	2832.8	
Cost Savings (\$)		162.7		143.3		218.5		524.5	
Cost Savings (%)		15.6		11.1		21.3		15.6	
Energy Savings (%)		7.1		8.5		14.0		9.6	
Peak Demand Cost Reduction (%)		26.6		15.2		29.8		23.6	

#### Notes

- Relatively low energy savings because RTUs are identical
- Large demand savings peak even in peak summer month because of unit oversizing



## **Accomplishments – Simulated Short-term Results for HG**



# **Accomplishments – Simulated Summer Results for HG**

	June		Jul	У	Au	gust	3-Month Totals		
	Conv	PnP	Conv	PnP	Conv	PnP	Conv	PnP	
Energy (MWh)	6.7	5.2	8.2	6.1	7.4	5.5	22.3	16.9	
Energy Cost (\$)	669.2	523.6	820.5	614.5	737.1	554.3	2226.8	1692.4	
Peak Power (kW)	30.0	20.7	30.3	21.1	30.6	30.0	-	-	
Demand Charge (\$)	360.4	248.6	364.2	252.8	366.8	359.9	1091.4	861.2	
Total Cost (\$)	1029.6	772.2	1184.7	867.3	1103.9	914.1	3318.1	2553.6	
Cost Savings (\$)		257.3		317.4		189.7		764.5	
Cost Savings (%)		25.0		26.8		17.2		23.0	
Energy Savings (%)		21.8		25.1		24.8		24.0	
Peak Demand Cost Reduction (%)		31.0		30.6		1.9		21.1	

#### Notes

- Significant energy savings due to greater operation of more efficient RTU1
- Significant demand savings except in month having peak cooling (Aug)



## **Progress and Accomplishments**

Market Impact: Have established collaborations with commercial partners and their end-use customers to further develop implementation paths and set up additional demonstrations. Working with:

- Field Diagnostics Services, Inc. (FDSI) to set up enterprise solution for Bank of America using existing EMS infrastructure
- FDSI to set up and demonstrate cloud-based solution using webenabled thermostats
- FrontStreet Facilities Solution to set up and demonstrate cloudbased solution for a national retail account



# **Project Integration and Collaboration**

**Project Integration**: Closely working with commercial collaborators to further market demonstration and deployment

**Partners, Subcontractors, and Collaborators**: Purdue is responsible for algorithm development and evaluation; Virginia Tech is developing reduced-order indoor air modeling; ORNL provided access and support for field site demonstrations and assessments; FDSI and FrontStreet are working with end-use customers to establish implementation requirements and set up future demonstrations

**Communications**: The RTU Coordinator was presented in a seminar at the ASHRAE Winter Meeting, 2015.



### **Next Steps and Future Plans**:

- Demonstrate cloud-based implementation requirements and savings opportunities for a retail store managed by FrontStreet Facilities Solution
- Demonstrate enterprise solution with FDSI for Bank of America (BOA) using existing EMS infrastructure



# **REFERENCE SLIDES**



Energy Efficiency & Renewable Energy

### Project Budget: \$350,000 Variances: None Cost to Date: \$350,000

Budget History										
	<b>23 (past)</b> - 4/30/2014		<b>(current)</b> - 4/30/2015	<b>CBEI BP5 (planned)</b> 5/1/2015 – 4/30/2016						
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share					
		\$350,000	\$22,000	\$200,000	\$22,000					

CBEI – Consortium for Building Energy Innovation (formerly EEB Hub)

**BP – Budget Period** 



Energy Efficiency & Renewable Energy

## **Project Plan and Schedule**

• Go/No-Gos completed on October 20, 2014 and February 28, 2015

Project Schedule												
Project Start: 5/1/2014		Comp	Completed Work									
Projected End: 4/30/2016		Active Task (in progress work)										
		Milestone/Deliverable (Originally Planned) use for missed milestones										
		Milestone/Deliverable (Actual) use when met on time										
		BP3 (2	013-14	L)		BP4(2	014-15	5)	CB	EI BP5	(2015	-16)
Task	Q1 (Feb-Apr) Q2 (May-Jul) Q3 (Aug-Oct) Q1 (May-Jul) Q1 (May-Jul) Q2 (Aug-Oct) Q3 (Nov-Jan)		Q4 (Feb-Apr)	Q1 (May-Jul)	Q2 (Aug-Oct)	Q3 (Nov-Jan)	Q4 (Feb-Apr)					
Past Work												
Model and Control Development												
Control and Testbed Assessments								•				
Cooling -Side Load Meter Evaluation												
Current/Future Work												
Tools & Processes for Prioritizing Sites												
Prioritize Bank of America Sites												
Deploy RTU Coordinator at Pilot Sites												
Assess Performance												

**BP – Budget Period for Consortium for Building Energy Innovation (formerly EEB Hub)**