

ET R&D project in support of DOE/BTO Goal of 50% Reduction in Building Energy Use by 2030.





CRADA project with Trane TOP US Commercial HVAC Equipment OEM

# Next Generation Rooftop Unit – CRADA

### **Bo Shen**

Oak Ridge National Laboratory shenb@ornl.gov; 865-574-5745 April 3, 2013

U.S. DEPARTMENT OF EN ENERGY Re

Cooling

Packaged Units

54%

Other

46%

Problem Statement: half of all US commercial floor space cooled by packaged AC units, consumes more than 1.0 Quad source energy/year; highly efficient systems needed to facilitate DOE/BTO goal for 50% reduction in bldg. energy use by 2030.

### Impact of Project:

- > An estimated 40,000 10-Ton RTUs sold per year.
- If companies only buy best in class 10-Ton RTUs, they save about \$50 million a year in energy costs.
- > A typical 100,000 sq. ft. large box retail building contains 20-Ton RTUs.

### Project Focus - Support DOE RTU challenge:

- Development & market implementation of High Efficiency RTUs (10-ton to 20-ton, 20.0 IEER) with up to 50% energy savings vs. min. efficiency systems.
- 2. Development of advanced RTU model library, analytical tools support of DOE RTU challenge.

# Equipment Development and Performance Testing

 Our goal is > 20.0 IEER, up to 20-ton cooling capacity, cost-effective (20-ton high efficiency RTU development is a bigger technical challenge).

# Analysis Tools Development to Enable Best Practices

- Simulation-driven product development, to shorten development cycle and optimize product performance.
- Enable development of whole product family.
- Performance mapping using fundamental, first-principle, hardware-based equipment model, to reduce testing cost and accelerate market deployment.

# Approach

**ENERGY** Energy Efficiency & Renewable Energy

### Approach:

- 1. Extensive modeling and comparison of various system configurations.
- 2. Laboratory performance testing to validate the tools and verify the energy saving / efficiency (the project metrics).
- 3. Building energy simulations to reveal energy savings.

## Key Issues:

- High part-load operation efficiencies.
- Decreasing air flow by specifying variable air volume rather than constant air volume.
- Increasing fan efficiency from 45% efficiency to premium efficiency.


### **Distinctive Characteristics:**

- Highly modulated system to best utilize HX surface area at part-load conditions.
- Combining a tandem (15-ton) and a variable-speed vapor compression system (5-ton) as a cost-effective option for capacity modulation.

# Approach (DOE/ORNL HPDM)

U.S. DEPARTMENT OF

Energy Efficiency & Renewable Energy





# Approach (ORNL Advanced RTU Component Model Library)


U.S. DEPARTMENT OF


Energy Efficiency & Renewable Energy

#### Arbitrary HX Circuitry -- Segmented Fin-&-Tube Coil Modeling









### Segmented MHX Modeling

**Desiccant-coupled** Wheel On-Off Cooling RTU for Control Coil Supply-Air to Space 3 Wheel **By-Pass** Dessicant Wheel Pre-Heat Return Air Coil From Space

Variable-speed compressor modeling - High-efficiency permanent magnet motors (integrate OEM's proprietary DLL to our system modeling)

# Approach (Laboratory Performance Testing)

U.S. DEPARTMENT OF

Energy Efficiency & Renewable Energy




- ORNL is the only DOE lab, having a facility capable of testing RTUs up to 20-ton.
- Performance testing work to be done in summer, 2013 (pictures from other project work).

# Approach


Analytical evaluation of 10 technical solutions (HPDM)

- Innovative component technologies: variable-speed compressors, microchannel HXs, condenser evaporative pre-cooling, desiccant wheel, etc.
- Cost-effective modulation strategy: tandem system (15-ton) provides major modulation; small VS system (5-ton) provides fine tuning.



# Approach

Energy analyses completed to establish pathway to performance targets (EPlus Simulations)



- Baseline Single-speed RTU, IEER of 11.2, in commercial, small office buildings
- Only list the savings in vapor compression systems, not including savings by fans, economizer, etc.



## Accomplishments:

- 1. RTU component & equipment model library ready to support public use.
- 2. ORNL's concept design finished.
- 3. Building energy simulations done to reveal saving potentials, based on the concept design.
- 4. CRADA agreement signed with Trane (Sept/2012).

# Progress on Goals:

- 1. ORNL's concept design is being evaluated by the CRADA partner during their product development.
- 2. ORNL has applied the ORNL concept to the Trane equipment by setting up the ORNL model and calibrating to their baseline equipment.

# Project Plan & Schedule

- **ENERGY** Energy Efficiency & Renewable Energy
- Original initiation date (analytical support for RTU challenge) 01-Oct-2010; Planned completion date 30-Sept-2013
- Extension to 30-March-2014, to complete laboratory testing on a breadboard unit, final model calibrations, building energy simulations and economics assessments, and finalization of draft report.
- Reason for slipped milestones and slips in schedule delayed completion of CRADA agreement signed in September 2012

Summary						Legend						
WBS Number or Agreement Number						Work completed						
Project Number 18810							Active T	iask				
Agreement Number 6800							Milestones & Deliverables (Original Plan)					
						Milestones & Deliverables (Actual)						
		FY20	.012			FY2013				FY2014		
Task / Event	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)	Q1 (Octt-Dec)	Q2 (Jan-Mar)	Q3 (Apr-Jun)	Q4 (Jul-Sep)
Project Name: Next Generation Rooftop Unit												
Complete overall rooftop unit model development	•		,		,			,				
Rooftop unit concept design (IEER = 20)			['		· '			·′	· '		· [	
Building energy simulations based on concept design			/		<u> </u>			′				<u> </u>
CRADA agreement with Trane signed					//			′				<u> </u>
Current work and future research												
Finish 20-ton RTU product design			<u> </u>					′				
Complete lab tests of prototype RTU			<u> </u>		<u> </u>							
Building energy simulations and economics assessments			<u> </u>		<u> </u>							
Go/no-go decision to proceed to field test			<u> </u>		<u> </u>			<u> </u>				



Project Budget: \$1072k FY11-FY13 total Variances: none so far Cost to Date: ~\$532k through February 2013 Additional Funding: none so far

Budget History									
F	Y2011	F	Y2012	FY	2013	FY2014			
DOE	Cost-share*	DOE	Cost- share*	DOE	Cost- share*	DOE	Cost- share*		
\$122k	\$0k	\$500k	*	\$450k	*	\$0k	*		

\* In-kind contribution from CRADA partner – confidential information

Energy Efficiency & Renewable Energy

Partners, Subcontractors, and Collaborators: CRADA partner is the Trane Company, Ingersoll Rand.

Technology Transfer, Deployment, Market Impact: Ultimate target is to enable development and market entry of high efficiency (IEER > 20.0) RTU system option aimed at commercial bldgs. by 2015.

**Communications:** Regular monthly progress reporting to DOE and Trane; and two publications:

- B. Shen, K. Rice, E. Vineyard, "Development of 20 IEER Rooftop Units A Simulation Study", International Refrigeration Conference at Purdue, 2012.
- B. Shen, K. Rice, E. Vineyard, "Development of 20 IEER Rooftop Units System Modeling and Building Energy Simulations", submitted to International Journal of HVAC&R.




### Next Steps and Future Plans:

# -Complete testing of the prototype unit– September 2013

- -Calibrate RTU equipment model to test results November 2013
  - Control strategy development
  - Equipment performance mapping
- -Assess building energy savings and economics- March 2014
  - EnergyPlus building energy simulations in sixteen US cities
  - Payback periods estimates

-Go/no-go decision to proceed to field test using ORNL's Commercial Flexible Research Platform – March 2014





Hardware-based HPDM/Modelica model library to support RTU design, building control strategy development, fault diagnosis, etc.