


Flexible Assembly Solar Technology

Binyamin Koretz
Director, Strategic Planning & IP



BrightSource
Limitless





Project Overview

- Project title: Flexible Assembly Solar Technology
- Goals: Develop and demonstrate transportable and field-deployable heliostat reflector assembly systems
- Awardees: BrightSource Construction Management and BrightSource Industries Israel
- Key subcontractor : Grenzebach
- Principal Investigator: Elad Toister, BSII
- Project start date: June 2012
- Current status: preliminary design




About BrightSource Energy

- We develop and build solar thermal projects using our own central tower technology
- Headquartered in Oakland, CA, with R&D, engineering, project management and supply chain management in Jerusalem, Israel
- Founded by key managers of 1980s solar thermal pioneer Luz International





Ivanpah SEGS Complex



- 3 x 130 MWe towers in the Mojave desert of California, 50 miles SW of Las Vegas
- Forced-recirculation drum-type boilers with SH to 560°C @ 160 bar and RH
- 140m towers
- 173,500 heliostats, each 15m²



Heliostat assembly at Ivanpah





FAST Project in the context of overall cost reduction



BrightSource
Limitless



Comparison of LH-2.3 to LH-2.2 (Ivanpah)




	LH-2.2	LH-2.3	% change
Mirror dimensions	2300 x 3300x 4mm	2600 x 3660 x 4mm	
Reflective area per heliostat	15.2 m ²	19.0 m ²	+25%
Gap between mirrors	300 mm	30 mm	-90%



Net result: fewer heliostats for same output

A closer look at the LH2.3 Heliostat Reflector

LH2.2



LH2.3





Solar field installation


Major steps:

1. Mirror assembly
2. Flexible on-site reflector assembly
3. Pylon insertion
4. Final reflector installation



1. Mirror assembly


- Diagonals fold into support arm for transport efficiency
 - Single design supports all focal lengths



Designed to enable on-site transportability and FAST deployment




Mirror assembly



30 mirror sub-assemblies/Crate



2. Flexible on-site reflector assembly



Manual 'alpha' prototype used at our test facility

150 LH2.3 heliostats
assembled and tested






3. Pylon insertion


Ivanpah:

Drilling & Driving – 2 separate steps





4. Final reflector installation



Thank you



BrightSource
Limitless