




Thomas Bialek, Ph.D., P.E.
Chief Engineer, Smart Grid



SDG&E's Microgrid Activities
DOE Electricity Advisory Committee
October 20, 2011

CUSTOMER EMPOWERMENT


Figure 6-4



Future Microgrid?



SDG&E's SMART METER Home Area Network (HAN)



Project Summary

Utilize advanced technologies to integrate and manage distributed resources within the Smart Grid




Budget:

\$7.5M DOE and \$2.8M CEC plus matching funds from SDG&E and partners

Benefits:

- Integrate and leverage various generation and storage configurations
- Reduce the peak load of feeders and enhance system reliability
- Enable customers to become more active participants in managing their energy use



Microgrid Design



Requirements


- Define microgrid boundary
 - Industrial customer, campus, substation, circuit
- Match load and generation
 - Voltage, frequency and power factor within tolerances
- Define reliability requirements
 - SAIDI, SAIFI, MAIFI and power quality
- Determine seamless transition
 - How long to restore power in island
- Define loads
 - Critical, demand response, peak load
- Determine island duration
 - Typical outage or extreme event
- Define generation needs
 - Renewables, energy storage, fossil generation

Site Selection – Borrego Springs, CA



Key Strengths:

- Progressive-minded community
- High concentration of customer-owned solar generation
- Potential for reliability enhancements
- Opportunity to balance supply and demand to be more self-sufficient
- Extendable to service territory



Borrego Springs



Rooftop PV Systems



Ground Mounted PV Solar Array



Project Components



Distributed Energy Resource (DER) and VAR Management

- Two 1.8 MW Tier 1 Caterpillar 3516DITA diesel generators owned by SDG&E
 - 200 hours per generator per year
 - Upgrading to meet Tier 4 emissions and to be remotely operable
 - ✓ Delivered generators to Borrego Springs, October 2011
- SCADA Capacitors
 - Standards evaluating pilot installations

Advanced Energy Storage

- Commercial/Substation-Sized (~ 1500 kWh)
 - Execute agreement, October 2011
 - Install batteries, Q2 2012
- Community or Neighborhood-Sized (3 @ ~ 50 kWh)
 - ✓ Executed agreement, August 2011
 - Install batteries, Q1 2012
- Home (5 @ 5-10 kWh) – finalize agreement with preferred vendor, October 2011

Project Components



Feeder Automation

- To utilize FLISR with new OMS/DMS system


Customer Energy Management/Price-Driven Load Management (PDLM):

- 125 customers to participate in testing how pricing signals can/may alter customer usage
- Executed agreement with the University of San Diego, August 2011
- Executed agreement with Pacific Northwest National Laboratory (PNNL), September 2011
- Finalize agreement for PDLM solution with preferred vendor, October 2011

Microgrid Controller

- To be located at Borrego Springs Microgrid Yard, self-contained
- Finalize requirements with Oracle
- Complete design, Q4 2011

Managing a Microgrid



Update on 2011 Milestones



- ✓ Obtained Stationary Source Permit from San Diego County APCD, Q1
- ✓ Constructed noise abatement wall, Q2
- ✓ Executed agreement for the development of the Microgrid Controller, Q2
- ✓ Complete site development of generator portion of microgrid yard, 9/11
- ✓ Install generators, 10/11
- Initial testing of generators, 10/11
- Complete design of the Microgrid Controller, Q4
- Recruit customers to participate in Home Area Network demonstration, Q2 2012
- Install batteries, Q2 2012

Schedule



	2010		2011				2012				2013	
Description	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	
Engineering and Design	[Bar spanning Q3 2010 to Q4 2011]											
Installation and Testing				[Bar spanning Q2 2011 to Q3 2012]								
Demonstration						[Bar spanning Q4 2011 to Q3 2012]						
Reporting									[Bar spanning Q3 2012 to Q4 2012]			

Acknowledgements



- **Acknowledgement:** “This material is based upon work supported by the Department of Energy [National Nuclear Security Administration] under Award DE-FC26-08NT02870 and DE-FC26-08NT01904.
- **Disclaimer:** “This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States government or any agency thereof.”

LEGAL NOTICE

This report was prepared as a result of work sponsored by the California Energy Commission (Energy Commission). It does not necessarily represent the views of the Energy Commission, its employees, or the State of California. The Energy Commission, the State of California, its employees, contractors, and subcontractors make no warranty, express or implied, and assume no legal liability for the information in this report; nor does any party represent that the use of this information will not infringe upon privately owned rights. This report has not been approved or disapproved by the Energy Commission nor has the Energy Commission passed upon the accuracy or adequacy of the information in this report.

COPYRIGHT NOTICE

© 2010

Questions?



Thank You



Tom Bialek

Chief Engineer, Smart Grid

tbialek@semprautilities.com

www.sdge.com/smartgrid/

