	Rating Element	Criteria for Maximum Rating
	COST	
A1	Cost Estimate	A cost estimate has been developed and formally approved by DOE and is the basis for the cost baselines. The cost estimate is a reasonable approximation of Total Project Costs, and covers all phases of the project. The estimate is prepared in accordance with DOE requirements. The estimate bases are fully documented and traceable and supporting backup information has been collected and organized and is available in a central file or location. Major estimate assumptions, especially those affecting major cost drivers, are fully documented and explained. Estimate exclusions or qualifications are clearly documented. Estimated costs are time-phased and escalated using current DOE escalation rates.
A2	Cost Risk/Contingency Analysis	The cost estimate includes contingency allowances developed in accordance with DOE guidance. In addition to any deterministic contingency analyses that may have been developed, a probabilistic risk analysis has been performed. The assumptions, rationale and methodology used to perform the probabilistic analysis are explained. The cost risk analysis builds on and is tied to the Project Risk Management Plan. Risk mitigation costs, if appropriate, have been included in the baseline cost estimate, or addressed by the risk analysis model. Costs related to schedule contingency are also included, as discussed under B-5. The confidence level of the baseline cost estimate is clearly stated and explained. All of the preceding requirements are documented in the project record.
A3	Funding Requirements/Profile	Funding requirements have been defined and the project timeline is in compliance with the DOE budget timeline/process. Required budget documentation, including Project Data Sheets (where required), reflects current project cost and schedule estimates/forecasts. The funding profile is based on quantified resource requirements derived from the cost estimate, time-phased through integration with the project baseline schedule. Resource constraints (personnel, budget authorizations, etc.) have been considered when developing the project schedule, and an iterative process used to correlate the cost estimate, schedule and funding profile. The funding profile is based on full consideration of available or expected budget or funding levels for the project. The impact of any projected funding shortfalls have been assessed and management strategies developed to accommodate those shortfalls have been considered and incorporated in the project plans. All of the preceding requirements are documented in the project record.
A4	Independent Cost Estimate/Schedule Review	In addition to any internal cost and schedule estimate reviews, the cost estimate and schedule have been subjected to an independent review by an organization not directly involved with the project (ICE, EIR, IPR, as required). The independent review has been documented, including the techniques used and type of review performed. The results, findings and recommendations of the independent review have been reconciled with the cost and schedule estimates and cost estimate and schedule changes incorporated.

	Rating Element	Criteria for Maximum Rating
A5	Life Cycle Cost	The project Life Cycle Costs (LCC) have been rough-order-of-magnitude estimated, including relevant assumptions, bases of estimate, qualifications, and exclusions. LCC includes the estimated cost for government commitments that result from execution of this project, including downstream projects/facilities and eventual disposition of the facilities constructed for this project. The LCC estimate should meet the requirements of Office of Management and Budget directives and DOE Orders and guidance. LCC of competing projects or alternative strategies are estimated and documented on a comparable basis.
A6	Forecast of Cost at Completion	After the cost baseline is approved and the measurement of actual performance is begun, forecasts of costs at completion (actual costs to-date plus "to-go" costs) are developed and issued at regular intervals. Cost forecasts are developed in accordance with project procedures. Key assumptions supporting the baseline estimate are periodically re-evaluated and the impact of changing assumptions are reflected in the estimates of "to-go" costs. Forecasts are related to the Change Control system and incorporate both approved and pending changes, as appropriate. The forecast of cost at completion is a reasonable projection based on the status of the project and the experience to-date.
A7	Cost Estimate for Next Phase Work Scope	A detailed cost estimate is prepared and approved for costs for the work scope to be accomplished during the next phase of the project (i.e., the efforts needed to successfully complete the prerequisites for the next Critical Decision). Cost estimates are defensible with an appropriate level of supporting detail and documentation.
SC	HEDULE	
B1	Project Schedule	A schedule has been developed and approved by DOE, is consistent with regulatory milestones, and is the basis for the Schedule Baseline. The schedule is a reasonable layout of project activities for all phases of the project and is at a level of development expected for the project stage. Project activities are included consistent with the WBS, and the schedule is prepared in accordance with DOE guidance and practices. The schedule is activity-based and includes milestones, reasonable durations and acceptable logic. Lower level schedules are developed and tiered to support the baseline schedule and/or Project Master Schedule. Project-specific conditions are included. Assumptions are defined. An appropriate method of developing the schedule is used including an acceptable software package when applicable.
B2	Major Milestones	Milestones are included at each level of the project schedule to establish a baseline and indicate significant progress against the work to be completed. Stakeholder and regulatory milestones are included as appropriate. Milestones are tiered to support project decisions, performance, approvals, etc. A milestone dictionary is provided which defines the requirements for successful completion. An appropriate number of milestones is included to control the project.
В3	Resource Loading	The schedule is resource loaded, considers critical resources, and is consistent with the funding profile. The resource loading is documented, and is reasonable considering such elements as ramp-up, lead times, constraints, etc.
B4	Critical Path Management	A Critical Path is defined. Near-Critical Path activities are identified and sensitivity analyses have been conducted. Schedule management practices are properly focused on Critical Path and Near-Critical Path activities.

	Rating Element	Criteria for Maximum Rating
B5	Schedule Risk/Contingency Analysis	A risk assessment has been conducted on the baseline schedule, and appropriate contingency added as required. Assumptions, rationale, and methodology, used in the analysis are documented.
B6	Forecast of Schedule Completion	After the schedule baseline has been approved, and the measurement of actual performance has begun, forecasts of completion dates are developed and issued at regular intervals in addition to presentations of schedule progress. Schedule forecasts reflect actual performance to date, and projections. Forecasts are related to the Change Control system and incorporate both approved and pending changes.
В7	Schedule for Next Phase Work Scope	A detailed schedule is prepared and approved for activities to be accomplished during the next phase of the project (i.e., the efforts needed to successfully complete the prerequisites for the next Critical Decision). The schedule is defensible with an appropriate level of supporting detail and documentation.
SC	COPE/TECHNICAL	
C1	Systems Engineering	Systems engineering is used to transform mission operational requirements or remediation requirements into system architecture, performance parameters, and design details. Beginning with the definition of a need, the systems engineering process is viewed as a hierarchy that progresses through a baseline and ends with verification that the need is met, including interfaces, fit, and completeness. The application of systems engineering to a project is tailored to the project's needs and documented.
C2	Alternatives Analysis	Major alternatives have been identified and viable alternatives have been analyzed. Alternative Analysis includes comparisons of LCC, Feasibility (including Technology Development requirements), Stakeholder Values, Safety, Regulatory Compliance, and other factors as appropriate. The preferred option(s) is identified and justified.
C3	Functional & Performance Requirements (What)	Functional and performance requirements for the project are documented, approved (by users, key stakeholders, and the DOE program office as appropriate) and under configuration control.
C4	Site Location	The geographical location of proposed project is defined and approved. The decision process is documented, as appropriate. The site selection process is considered a viable option and relative strengths and weaknesses of alternate site locations were assessed.
C5	Design Basis (How)	Project design basis developed and reviewed including appropriate level of approval from users, key stakeholders, site management, and DOE. Design Basis should clearly define key performance expectations and provide a sound framework for subsequent design activities. Design basis may also be subject to peer review by appropriate technical experts.

Rating Element			Criteria for Maximum Rating
C6	Design Criteria (How To)	Requirements and guidelines that govern des have been appropriately approved. Criteria ir	ign of the project reviewed by users and appropriate disciplines and criteria clude items such as:
		 Regulations DOE Orders 	4. Engineering StandardsDOE
		3. Codes and StandardsNationalState, Local	• Contractor
C7	Technology Needs Identified	Availability of new technology for project evalue each alternative documented.	uated, including benefits and risks. Technology development requirements for
C8	Technology Needs Demonstrated	New technology tested and determined to meet to be used on project evaluated and factored	et project objectives (technical, cost and schedule). Maturity of new technology into risk analysis.
С9	Trade-Off/Optimization Studies	overall project cost/schedule. These trade-off	ed to reach a reasonable level of project risk consistent with project phase and studies are a part of conceptual and later design phases to optimize the design de alternative design and process control and optimization approaches with s.
C10	Plot Plan	Plot plan is complete and shows location of p	roject in relation to adjoining facilities. It should include items such as:
		S Plant grid system with coordinates	S Green space
		S Unit limits	S Buildings
		S Gates and fences	S Major pipe racks
		S Off-site facilities	S Laydown areas
		S Tank farms	S Construction/fabrication areas
		S Roads and access waysS Rail Facilities	S Major utilities
C11	Process Flow Diagrams (PFDs)	Process flow diagrams completed and annota S Major equipment items S Flow of materials to and from the major ed	ted with material balances for design basis. Drawings include items such as:
		PFDs reviewed, approved and issued with a	t least Rev. 0 status - as an engineering control document. Any changes to lesign effort are reflected in revised drawings.
C12	Layout Drawings and Equipment List	finalized. All appropriate parties affected by e	nent drawings that identify locations of each item of equipment are complete and quipment placement (operations, maintenance, etc.) have had the opportunity. The facility, systems and major component equipment list is complete.

	Rating Element	Criteria for Maximum Rating
C13	Piping & Instrumentation Diagrams (P&ID)	Final version of revised P&IDs are available. P&IDs include all changes identified from the preliminary hazard analysis (PHA), and the maintenance and operations review. Comprehensive reviews completed and results incorporated. Examples of these reviews include (but are not limited to), Safety Analysis Reports, maintenance and operations requirements, and final construction and fabrication detail reviews.
C14	Site Characterization (Including Surveys and Soil Tests)	Assessment of site-specific requirements completed. Survey and soil test evaluations of proposed site completed. Investigation and development of site-specific characteristics sufficient to support final design and key assumptions are clearly documented. For example, limited soil borings (or samples) may have been taken. Evaluation and results of investigation characterize the following: S Hydrology S Underground obstructions S Geology (soil bearing characteristics) S Seismic
C15	Waste Characterization/Assess Current Situation	Waste and materials (if present) sufficiently characterized to identify appropriate disposition alternatives. Soil samples taken and evaluated to identify presence of hazardous substances (both radiological and chemical). Necessary plans and actions have been taken to confirm conditions, prepare documents and perform the discovery action, including resolving surveillance and monitoring activities and safety considerations.
C16	Waste Acceptance Criteria (WAC) and Waste Packaging	The on-site or off-site Waste Acceptance Criteria is documented, approved, and the requirements included into the design requirements for the project. The waste packaging requirements are identified, documented and included into the project design. All outstanding modifications to requirements are addressed.
C17	Hazard Analysis	Hazard analysis completed and reflected in final design. Analysis addresses all significant risks (chemical, nuclear/radiological, industrial, etc.) associated with the project as well as the operation of the completed project.
C18	Hazard Classification	Hazard classification defined, completed and approved. Results incorporated in technical baseline.
C19	Safety Documentation	Required nuclear and chemical safety documentation is complete and approved in accordance with DOE Orders. The Safety Analysis required input is completed, and requirements are developed along with the design, and proper considerations for safety envelope are "designed in." Comments are resolved and the results are incorporated into the necessary design documentation in support of Safety Documentation.
C20	Safeguards & Security	Security approach and potential requirements documented to aid in development of safeguard and security plan. Safeguard and security requirements identified and documented including vulnerability analysis and verifications, and incorporated into detailed design drawings and specifications.

	Rating Element		iteria for Maximum Rating
C21	ES&H Management Planning (including ISMS)	included in the facility and process design requiren approved. Integrated Safety Management Syste Safety Plans for integrating safety management inc thorough and an integral part of the design effort. clearly communicated.	s delineated in Federal, DOE, state, site and local laws and regulations are nents. Any exceptions to ES&H requirements are documented, justified and em (ISMS) implementation fully planned in accordance with DOE Orders. cluding fire, occupational, radiological, industrial hygiene, etc., are completed, The requirements, methodology, and responsibility for ES&H activities are
C22	Emergency Preparedness	preparedness planning is complete for the constru	gency preparedness adequately identified and documented. Emergency ction phase of the project and emergency planning for post-construction has d with site and external emergency response organizations, as appropriate.
C23	NEPA Documentation	NEPA activities, including NEPA strategy and rec	uirements, completed compliant with DOE Orders, as necessary.
C24	Civil, Structural and Architectural	Architectural Requirements; civil/structural required documented.	rements; seismic and other natural phenomena design requirements are
C25	Mechanical (Piping)	Process/mechanical design requirements, as applissued for construction: S. Mechanical Design Requirements S. Mechanical Equipment List S. Piping Specialty Items List S. Piping system criteria S. Valve List with tag numbers S. Tie-in List for all piping tie-ins to existing lines	S Piping stress analysis S Specifications (design, performance, manufacturing, material, and code requirements) S Utility Flow Diagrams S Utility Sources with Supply Conditions
C26	Instrument & Electrical	Instrument and Electrical requirements, as appropronstruction: S Electrical Area Classifications S Substation Requirements S Electrical Design Requirements S Electrical One-Line Diagrams	oriate, including, but not limited to the following, are approved and issued for S Substation Design S Instrument Index S Logic Diagrams S Instrument and Electrical Specifications
C27	Long Lead/Critical Equipment & Materials List	All long lead/critical engineered equipment and/o project schedule.	r materials are fully specified, bid, and tabulated as necessary to support
C28	Design Completion	Design documentation completed, including corengineering files, trade-offs, calculations, etc.	astruction packages, drawings and specifications. Back-up files include

	Rating Element	Criteria for Maximum Rating
C29	Design Reviews For Current Phase	Design reviews as appropriate to the project phase (i.e., Conceptual, Preliminary and Final) are conducted and performed by multi-functional team and, if appropriate, external experts are utilized.
C30	Interface Planning and Control	System interfaces (consistent with System Design Descriptions) have been identified and defined, and, if necessary, an Interface Control Plan has been completed, approved and implemented.
C31	Operating, Maintenance, and Reliability Concepts	The concepts are documented and approved and appropriately documented in the design.
C32	Reliability, Availability and Maintainability (RAM) Analysis	If appropriate, a Reliability, Availability and Maintainability review has been completed. Results of the RAM incorporated into technical baseline.
C33	Transition and Startup Planning	Project strategy addresses critical issues for transition from construction to startup/testing to operations. Project transition strategy finalized. Initial start-up plan developed. At a minimum, the following critical issues are addressed: Subsystem/system turnover criteria and documentation Test acceptance criteria Turnover (transition) security issues (such as access control and subsystem/system isolation) Craft jurisdictional issues Integrated testing plans, etc.
C34	Pollution Prevention and Waste Minimization	Detailed waste minimization/pollution prevention plan for project and operations phases completed for selected design/project scope, as necessary. Describe, estimate costs for, and present implementation plan for design, operational, and mitigatory features that will minimize wastes and prevent pollution. Detailed waste management plan describing quantity and type of wastes expected to be generated and plans for waste treatment, storage and disposal completed. The plan should: S Support estimation of waste management costs for process as well as facilities. (Estimated costs considered in critical decision process.) S Identify project options for waste treatment, storage, and disposal, including an assessment of availability of future disposal capacity and sites. S Integrate waste management plans with waste minimization/pollution prevention plans. S Characterize regulatory benefits and concerns associated with types and quantities of wastes expected.
C35	Transportation Requirements	Transportation requirements including nuclear and hazardous materials identified and documented including both off-site and in-plant transportation, as well as methods and equipment (casks, overpacks, etc.) for receiving/shipping materials (e.g., rail, truck, air, marine).

	Rating Element	Criteria for Maximum Rating
C36	Loading/Unloading/Storage Facility Requirements	List of requirements identifying raw materials to be unloaded and stored; products to be loaded along with their specifications; cranes, remote handling equipment for the installation/removal or operation of process equipment. This list should include items such as: S Material Safety Data Sheets created S Specification of any required special isolations provisions S Instantaneous and overall loading/unloading rates S Details on supply and/or receipt of containers and vessels S Storage facilities to be provide and/or utilized
C37	Training Requirements	Training requirements defined, planned and scheduled. Design considerations have been incorporated as appropriate. Simulation and/or mockup facilities are defined and established as necessary.
C38	Processing/Production Plan/Schedule	Processing, Production Plan and Schedules available and include items such as: S All production/characterization/sampling steps are identified and integrated S Assumed throughput and production efficiencies are defined and reasonable S Assumptions are supported by time and motion studies, calculations and operating experience S Resource requirements for each step identified S Failure/reject rate assumptions documented and supported S Equipment and material needs including availability and reliability defined S Initial production plan formulated S Design approach has optimized processing and production objectives considering spare capacity
C39	Operations Plans and Procedures	Operating plans and procedures are defined and development plans are in place, including operating procedures that reference technical specifications and administrative limits, as necessary.
MA	NAGEMENT PLANNING AND CONTROL	
D1	Mission Need Statement	An approved mission need statement exists. Project mission need statement demonstrates that project supports execution of, and project need relates to Program Strategic Plan goals and objectives as well as the DOE Strategic Plan. Mission needs reassessed after major changes in program, at budget submission and at Critical Decisions.
D2	Acquisition Strategy/Plan	An Acquisition Strategy/Plan has been developed and approved in accordance with DOE requirements/orders. The acquisition strategy and plans should be sufficient to accomplish the project using a tailored approach. The project is in compliance with the site/complex strategic plan.
D3	Conceptual Design Report (CDR)	CDR reviewed and approved by contractor and DOE.
D4	Project Charter	A chartering mechanism has been developed and used to formally recognize the existence of the project. It empowers and holds the Project Manager responsible and accountable for ensuring successful project completion.

	Rating Element	Criteria for Maximum Rating
D5	Key Project Assumptions	A complete list is available of critical facts and circumstances that would affect project outcome if changed. These assumptions have been approved by appropriate parties. Project assumptions are reflected in technical/cost/schedule baselines and risk management plans.
D6	Project Execution Plan (PEP)	The PEP has been developed and approved in accordance with DOE requirements/orders. The PEP is the primary agreement on project planning and objectives between all parties, which establishes roles and responsibilities and defines how the project will be executed, including tailoring general requirements and processes to the specifics of the project
D7	Integrated Project Team/Project Organization	The project organization is in place and functional. The integrated Project Team is in place early in project phases. The project is staffed with sufficient numbers of project management, technical, and acquisition specialists suitably qualified to accomplish project objectives.
D8	Baseline Change Control	Acceptable process established to review and approve proposed changes to cost, schedule, and technical baselines to determine impact of changes. Baseline Change Control Boards (CCB) established at appropriate levels of organization, thresholds for each level defined, and appropriate procedures in place.
D9	Project Control	A functioning project control system is in place for managing project baselines using earned value techniques, variance analysis, contingency/reserve management and effective reporting in accordance with DOE Orders and guidelines.
D10	Project Work Breakdown Structure (WBS)	Project Work Breakdown Structure established and reflects the project through completion. WBS dictionary completed, including detailed Statements of Work (SOWs), project schedule and cost directly aligned with WBS structure, and deliverables defined.
D11	Resources Required (People/Material) for Next Phase	Resources required for next phase identified and are available.
D12	Project Risk Management Plan/Assessment	Risk management plan developed, included in Acquisition Plan and/or PEP as appropriate, and risk mitigation strategy in place. Project risk is an accurate and complete estimate of probability and severity of cost, schedule and other impacts associated with uncertainties in the project, including a time-frame in which these risks are expected to occur. Risks are tracked, reported, and controlled.
D13	Quality Assurance Program	A Quality Assurance (QA) program is established. QA factors, including standards, specifications, and limitations identified. Quality Control (QC) and QA oversight organization in place and functional.
D14	Configuration Management	A configuration management program established and functioning to ensure consistency among requirements, criteria, design, existing facilities, physical configuration, and interfaces within project documents.

	Rating Element	Criteria for Maximum Rating
D15	Value Engineering	Where appropriate, a value engineering program complying with DOE Orders is in place and qualified personnel have analyzed appropriate project functions using accepted industry techniques with the aim of improving performance, reliability, quality, safety and life cycle costs of products, systems or procedures.
		The value engineering analyses are documented in a formal report and have provided unbiased, outside opinion and/or senior expertise (as appropriate) as inputs to the design process and an independent review of concept, design, and schedule. Measures taken to minimize project cost and maximize the return on investment for delivering the project have been documented and cost savings have been quantified. Project criteria have been re-evaluated when value engineering analyses have determined them to have poor value or a high cost-to-worth ratio.
D16	Procurement Packages	Procurement packages are being developed in accordance with the procurement strategy. Contractor selection processes and procedures are in place. Procurement packages reflect all requirements for security, safety and environmental considerations and pass on appropriate responsibilities to contractors and subcontractors.
D17	Project Acquisition Process	The project is being accomplished in accordance with the established DOE Project Acquisition Process, including Critical Decisions and Energy System Acquisition Advisory Boards.
D18	Funds Management	A funds management system is in place to ensure funds are allocated to support the project baseline elements for the current fiscal year. A system is in place to periodically review the annual costs to ensure that the annual funding will not be exceeded.
D19	Reviews/Assessments	Reviews (including EIRs and IPRs) and assessments are performed (for the current phase) and the findings, assessments, and recommendations are documented and presented to appropriate levels of management. A Corrective Action Plan is in place and being tracked/managed as necessary. Appropriate reviews and self-assessments are planned/conducted as an integral part of the project, based on project complexity, duration and critical decision points.
E	TERNAL FACTORS	
E1	Integrated Regulatory Oversight Program	Applicable Federal, state, and local government permits, licenses, and regulatory approvals, including strategies and requirements are identified and obtained in a timely manner or milestone dates established. Schedule for receipt of authorization from regulators should be realistic based on experience. Requirements and milestone dates are updated as necessary and kept current.
E2	Inter-Site Issues	Key inter-site coordination issues identified, addressed and resolved or plans in place to accomplish resolution.
E3	On-Site Issues	Key on-site coordination issues identified, addressed and resolved or plans in place to accomplish resolution.
E4	Permits, Licenses, and Regulatory Approvals	Applicable permits, licenses, and regulatory approvals obtained and milestone dates for pending and new applications reviewed and revised as appropriate. All permits, licenses, and approvals necessary to construct and operate a facility or to initiate and perform project activities are identified and will be obtained when needed to continue project execution on schedule. Schedule for receipt of authorization from regulators should be realistic based on experience.

	,	
Rating Element		Criteria for Maximum Rating
E5	Stakeholder Program	Stakeholders identified and their relationship to project evaluated. Project's impact on stakeholder interests and potential
		stakeholder groups within community identified. Any required interfaces with external organizations or authorities identified
		and addressed. Based on available stakeholder information and size and scope of project, appropriate Public Participation
		Plan in place. Specific stakeholder group issues addressed relative to project goals and objectives, technical issues, project
		risk, and environmental strategies.