

# Sustainable Energy Resources for Consumers (SERC) – Solar Hot Water Heaters



**Presenter:**

**Eliza Hotchkiss, NREL  
Analyst**

**October 27, 2011**

# Solar Technologies



Solar Photovoltaics (PV)



Solar Hot Water (SHW)

# Solar Hot Water (SHW) Heat




Evacuated Solar Tube Collectors



Flat Plate Solar Collectors with Storage

# SHW Basic System Elements



- Collector (flat plate or evacuated tube)\*
- Storage tank\*
- Piping\*
- Controls\*
- Transfer Medium (glycol or water)
- Circulation method (gravity or pumped)



\* Often provided as pre-engineered(packaged) systems

# SHW Factors

- Availability of “solar resource”
- Efficiency of collector **system**
  - varies (pre-engineered)
- Cost of alternative fuels



# SHW Basic System Characteristics

Comparison of Solar Hot Water System Types				
Characteristic	Thermosyphon (gravity fed, simple system)	Active direct (pumps water)	Active indirect (pumps glycol)	Drainback (collector fluid can empty)
Low profile-unobtrusive		x	x	x
Lightweight collector		x	x	x
Survives freezing weather			x	x
Low maintenance	x			x
Simple: no ancillary control	x			
Retrofit potential to existing store		X	x	x
Space saving: no extra storage tank	x	X		

# SHW System Considerations

---

- ✓ Systems operate best with routine maintenance (annual)
- ✓ Make sure unit has an automatic vacation mode or heat dissipater
- ✓ Where possible avoid custom designed systems
  - Custom systems may require a qualified technician for servicing
- ✓ Systems are not intended to meet 100% of hot water load
  - Approximately 60-75% of the hot water load, depending on location and system efficiency

# Certified Solar Thermal Installers

North American Board of  
Certified Energy Practitioners  
(NABCEP)

*“A technician in good standing with the Public Utilities Commission who has successfully completed an approved solar thermal training course and carries a current license as a Master Plumber, Master Oil Burner Technician or Propane and Natural Gas Technician or is a class 2 or 3 nationally certified refrigeration technician.”*

Contact information for installers can  
be found at:

<http://www.nabcep.org/installer-locator>



# Key Considerations

---

- ❑ Require site inspection prior to installation
- ❑ Require *minimum* **system** warranty
- ❑ Reference *minimum* installation standards (certified installers)
- ❑ Differentiate between pre-engineered systems and 'custom' designs
- ❑ Specify systems *minimum* solar fraction
- ❑ Request unit pricing

# Field Verification Checklist Items

## Solar Thermal Post Evaluation Checklist

PROJECT INFORMATION				
Property Address				
System Brief Description				
Number of Panels				
Orientation				
Tilt				
Estimated annual kBTU from SRCC rating				
Solar Installer Company (if applicable)				
Inspector				
Inspection Date				
Time of Measurement				
Ambient Temperature				
Solar Radiation (W/m <sup>2</sup> )				
Temperature of Water at Panel (°F)				
Inspection Checklist				
Yes	No	N/A	General	Note
			Backup heater is either: <input type="checkbox"/> electric <input type="checkbox"/> natural gas <input type="checkbox"/> propane	
			Installation is of industry standard and workmanlike quality.	
			Collectors are optimized for performance without sacrificing aesthetics.	
			Installation is consistent with plumbing diagram.	
			Installation is consistent with manufacturers' instructions.	
			City inspection(s) have been passed: Permit # _____ Date _____	


# Field Verification Checklist Items

- ✓ Number of panels & the type of installation
- ✓ Modules permanently installed
- ✓ Brief description
- ✓ Background information



# Field Verification Checklist Items

- ✓ Additional system components: backup heater
- ✓ Quality workmanship
- ✓ Matches plumbing diagrams
- ✓ City inspection



# Field Verification Checklist Items

- ✓ System components are new
- ✓ Collectors are SRCC rated (OG-100 or OG-300)
- ✓ Insulation is properly restored
- ✓ Penetrations are sealed
- ✓ Pressure does not exceed 80psi
- ✓ Maintenance access exists



	<p>This product certified by the Solar Rating and Certification Corporation c/o FSEC, 1679 Clearlake Road Cocoa, FL 32922  (321)638-1537  www.solar-rating.org SRCC Document OG-100</p>	<p>Sample Solar Corporation P.O. Box 12345 Anytown, CA 97402 Model No.: Super Sample Gross Area: 3.72 m2 (40.00 ft2) Serial Number:</p>	<p>Clear Day Rating in Category C 8.6 kWh/day 29 kBtu/day</p>
--	---	---	---

<http://www.solar-rating.org/ratings/>

# Equipment and Installation



# Field Verification Checklist Items

- ✓ Confirm the roof is in good condition (10 years remaining, at least)
- ✓ Roof penetrations are sealed and flashed
- ✓ Collectors have good solar access



Poor Roof Condition



Good Roof Condition

# Field Verification Checklist Items


- ✓ Check for plumbing leaks
- ✓ Confirm pipes are appropriate materials for the job
- ✓ Check for pipe insulation, especially in unheated spaces



Leaking tank valve




Copper piping




Uninsulated pipes should be insulated

# Equipment and Installation



# Field Verification Checklist Items

- ✓ Electrical wiring should be up to code
- ✓ Check that fluids are appropriate for the system by comparing manuals/documentation and labels on maintenance logs or invoices





# User Documentation



# Field Verification Checklist Items

- ✓ Check for proper documentation and contact information
- ✓ Client education



# Questions?

---

Eliza Hotchkiss

[eliza.hotchkiss@nrel.gov](mailto:eliza.hotchkiss@nrel.gov)

(303) 384.7309