

Advanced 3D Geophysical Imaging Technologies for Geothermal Resource Characterization

April 22-25, 2013

This presentation does not contain any proprietary confidential, or otherwise restricted information.

Principal Investigator: Greg Newman, Michael Fehler

Organizations: LBL & MIT

Track Name

Project Participants and Collaborators:

Lawrence Berkeley National Laboratory
Massachusetts Institute of Technology
Iceland GeoSurvey (ÍSOR);
Reykjavík University;
Uppsala University;
TerraGen (Operator of the Coso Field);
Icelandic Power Companies

Project objectives

- Develop improved geophysical imaging method for characterizing subsurface structure, identify fluid locations, and characterize fractures
- Obtain the maximum amount of information from seismic and electromagnetic data by developing new joint inversion methodology
- Apply the new method to four sites
 - Improve methods by application to real data from differing environments
 - Demonstrate applicability of methods

- Multi-steps for combined analysis
 - Individual analysis of geophysical datasets for 4 sites
 - Integrated interpretation
 - Iterative analysis using output of one method as input to another
 - MT <-> Seismic
 - Joint Imaging for common structure
- Analysis methods used
 - MT inversions for resistivity
 - Double-difference tomography (DDT) using micro-earthquake sources
 - Fully coupled elastic inversion


Four Regions Being Studied

- Krysuvik & Hengill Reykjanes area, Iceland
 - Several producing geothermal fields
 - Collect new MEQ data, leverage with existing MEQ data from ISOR Network & MT data
- Krafla volcano, Iceland
 - Producing Geothermal field
 - First Iceland Deep Drilling Project (IDDP) well
 - Use existing MEQ and MT datasets
- Coso Hot Springs, USA
 - Producing geothermal field
 - Analyze existing MEQ and MT data


Krafla

Original Planned Milestone/ Technical Accomplishment	Actual Milestone/Technical Accomplishment	Date Completed
Early in FY13	Krafla Model Appraisal (3D resistivity cube)	March FY13
Fall FY12	Krafla Joint MEQ-MT Analysis (initial results)	March FY13

Krafla Magma Chamber




Location of the Well in relation to the Magma Chamber




Krafla – Appraisal of Resistivity Cube


ISOR inversion




1D TEM/MT-DET inversion



LBNL inversion



UBC inversion



Geothermal zones

- The structures of the zones coincide
 - Resistive core
 - Deep conductive body under NW of IDDP-well

Dissimilarities


- Near surface
 - Very dependent on the initial model
- Edges and data coverage

Krafla:

Duke
2004-2005
2006-2007

UNC
2004

Borehole network
2008 and 2011





Joint Analysis of Krafla MT-MEQ Data

East-West Profile

Not Coupled to Resistivity Structure

Coupled to Resistivity Structure




- Sustained operation of 14 station MEQ network in the Reykjanes Peninsula
 - Area includes several producing geothermal power plants
 - Network installed in collaboration with Reykjavik University, ISOR, and University of Uppsala
 - Additional data from Iceland network
 - Over 2.5 years in operation , data quality excellent; operate until fall 2013







Krysuvik – Reykjanes

Original Planned Milestone/ Technical Accomplishment	Actual Milestone/Technical Accomplishment	Date Completed
March FY13	Krysuvik Resistivity-Velocity Model (initial results)	March FY13
March FY13	Continuously Operating MEQ Network – Reykjanes Area	March FY13


Seismicity During First Year of Network Operation



P and S Wave Velocity Models -- Krysuvik



Comparison Vp and Resistivity Krysuvik



Future Directions

TASKS	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
<i>Analysis in FY13</i>																								
1.1 Joint Imaging Framework Developments																								
1.2 Acquire Seismic Data - Reykjanes Peninsula																								
1.3 Decommission Seismic Reykjanes Network																								
1.3 Complete Joint MT-MEQ Analysis -- Coso																								
1.3 Complete MT-MEQ Analysis -- Krafla																								
1.4 Complete MT Anylysis Krysuvik Field																								
1.5 Start MEQ Analysis Krysuvik Field																								
1.6 Coso, Krafla,Hengill & Krysuvik MT Appraisal																								
<i>Analysis in FY14</i>																								
2.1 Complete MEQ Analysis of Krysuvik Field																								
2.1 Joint MT-MEQ Analysis of Krysuvik Field																								
2.2 Complete MEQ Analysis of Hengill Field																								
2.3 Joint MEQ-MT Analysis of Hengill Field																								
2.4 Coso, Krafla,Hengill & Krysuvik Appraisal																								
2.5 Quantify & Appraise Joint Image Uncertainty																								
2.6 Present Results at Technical Meetings																								
2.7 Prepare Technical Publicaitons																								

Milestone or Go/No-Go	Status & Expected Completion Date
Krysuvik Baseline MEQ/MT Modeling	MEQ Analysis Stated in February 2013
Pull MEQ Network	September 2013
Krafla Joint MEQ/MT Analysis	June 2013

Future Directions

TASKS	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
<i>Analysis in FY13</i>																								
1.1 Joint Imaging Framework Developments	█	█	█	█	█	█	█	█	█	█	█	█												
1.2 Acquire Seismic Data - Reykjanes Peninsula	█	█	█	█	█	█	█	█	█	█														
1.3 Decommission Seismic Reykjanes Network											█	█												
1.3 Complete Joint MT-MEQ Analysis -- Coso	█	█	█	█	█	█	█	█	█	█														
1.3 Complete MT-MEQ Analysis -- Krafla	█	█	█	█	█	█	█	█	█	█														
1.4 Complete MT Anylysis Krysuvik Field	█	█	█	█	█	█	█	█	█															
1.5 Start MEQ Analysis Krysuvik Field					█	█	█	█	█	█	█	█												
1.6 Coso, Krafla,Hengill & Krysuvik MT Appraisal					█	█	█	█	█	█	█	█												
<i>Analysis in FY14</i>																								
2.1 Complete MEQ Analysis of Krysuvik Field													█	█	█	█	█							
2.1 Joint MT-MEQ Analysis of Krysuvik Field													█	█	█	█	█	█	█	█	█			
2.2 Complete MEQ Analysis of Hengill Field													█	█	█	█	█	█						
2.3 Joint MEQ-MT Analysis of Hengill Field																█	█	█	█	█	█	█	█	█
2.4 Coso, Krafla,Hengill & Krysuvik Appraisal													█	█	█	█	█							
2.5 Quantify & Appraise Joint Image Uncertainty																	█	█	█	█	█	█	█	█
2.6 Present Results at Technical Meetings																	█					█		
2.7 Prepare Technical Publicaitons																						█	█	█

Milestone or Go/No-Go	Status & Expected Completion Date
Krysuvik Joint MEQ/MT Analysis	June 2014
Hengill MEQ Baseline Analysis	March 2014
Hengill Joint MEQ/MT Analysis	September 2014

- Correctly-formulated joint inversion has the capability to combine differing datasets to maximize the information obtained about geothermal targets
 - Useful for geothermal exploration, site characterization, and reservoir assessment
- Funded as comprehensive Icelandic/USA cooperative project under the International Partnership for Geothermal Technology (IPGT) agreement
- Participations from US, Iceland and Sweden
 - ISOR and RU funding from GEORG Program (GEOthermal Research Group) & Swedish Science Foundation
- Project Progress and Plans:
 - Complete Baseline MT & MEQ imaging
 - FY13 & FY14 will focus on joint interpretation/imaging of combined data – Krysuvik and Hengill.

Timeline:

Planned Start Date	Planned End Date	Actual Start Date	Current End Date
5/15/2010	9/30/2014	5/15/2010	9/30/2014

Budget:

DOE Share: \$3,205,226

Funding received in FY09: \$0

Funding for FY10: \$750,226

Funding for FY11: \$175,000*

Funding for FY12: \$830,000

Funding for FY13: \$725,000

Requested funding for FY14: \$725,000

Iceland/Sweden partners providing own funding & cost share

Federal Share	Cost Share	Planned Expenses to Date	Actual Expenses to Date	Value of Work Completed to Date	Funding needed to Complete Work
2/3	1/3	\$3,031,554 (DOE)	\$2,480,226 (DOE)	\$3,306,968 (DOE+Cost Share)	\$725,000 (DOE)