



Aviation Hangar Fire Tank Replacement Project



Lenny Farello

Agenda

- **Problem**
- **Site Plans**
- **Original System Description**
- **Options**
- **Impairment Plan**
- **Construction**
- **Acceptance Testing**
- **Issue**
- **Eglin AFB HEF Fatality Summary**
- **Foam System Trip – Video**
- **Questions???**

Problem




Problem

- Suspected structural concerns with original 500K gallon elevated dedicated fire water tank
- Internal inspections were not being performed as required
- KAFB trying to include 500K tank in the OST permit
- OST Management decision to replace dedicated fire water supply to hangar building versus accepting the risk

Site Plan



Site Water Utilities 1



Original Fire Systems in Hangar

- 34K square foot Aircraft Hangar – Now stores Two (2) 737's
- 500K elevated dedicated fire water tank (112' elevation to base of tank is about 48.5 psi suction to pumps)
- One (1) 2500 gpm @ 75 psi Electric Fire Pump for each Foam Deluge System for each Low Expansion Deluge Foam Sprinkler System (North & South)
- Four (4) UV/IR cross-zoned detectors positioned at aircraft wing level per deluge foam system
- Foam System Actuation via manual pull stations or cross-zoned UV/IR detectors
- Two (2) dead-man switches located in hangar (North & South)

Original Plan

- Re-connect original 14-inch hangar building feed main to the site domestic (KAFB) water supply
- Capacity of KAFB water supply was tested as Static=85psi with Residual=18psi Flowing=3664gpm
- Minimum required for 1 fire pump is 3750 (150%) at 20psi.
- Result – KAFB water supply is not adequate for hangar foam deluge systems
- No sprinkler system drawings or calculations available – As-builts created to determine design options
- System demand calculated at 6335gpm @ 128psi (both deluge LE foam systems operating)
- Result – Loss of Elevated Tank (48.5psi suction pressure) will require new fire pumps

Options

- Option 1: Install 2 new 120K gallon water tanks; Keep original Low Expansion Foam Deluge Systems; Upgrade to 2 new 350HP fire pumps; Keep original UV/IR Detection. \$1.3M
- Option 2A: Upgrade to High Expansion foam system; 2 new 51K gallon fire water tanks; Upgrade to 2 new 250 HP fire pumps; Convert deluge systems to single wet-pipe system; Keep original UV/IR Detection. \$1.5M
- Option 2B: Upgrade to High Expansion foam system (no tanks); Feed via KAFB water supply; Convert deluge systems to single wet-pipe system; Keep original UV/IR Detection. \$1.1M (Waivers Req'd)

Aviation Fire Suppression Water Design Update w/ Estimates

Design Option	Cost	Pro	Con
<p>#1: Install 2 new 120,000gal water tanks (~30' diameter each)</p> <ul style="list-style-type: none"> •Use original foam system •Upgrade to 2 new 350HP pumps 	\$1.3M	<ul style="list-style-type: none"> •Reliable (dedicated tanks) •Minimal downtime in hangar •Project cost will result in some electrical improvements 	<ul style="list-style-type: none"> •AF Exception Required (minimal risk) <ul style="list-style-type: none"> •Required 155psi exceeds ETL standard limit of 125 psi and will require AF AHJ approval •322 (AF) & Permit Modification for two new water tanks •Footprint taken off parking lot to accommodate tanks •Additional time and \$ to design for upgraded electrical systems. Delay of final design.
<p>#2A: Upgrade to High Expansion Foam system with dedicated water tanks</p> <ul style="list-style-type: none"> •2 new 51,000gal each (21' diameter) •2 new 250HP pumps (only 1 operates at a time) 	\$1.5M	<ul style="list-style-type: none"> •No AF Exceptions needed. Meets all AF standards and code requirements •Reliable (dedicated tanks) with a smaller footprint for tanks •Cleaner, state of the art foam system •Original electrical has the capacity to support the new pumps 	<ul style="list-style-type: none"> •Maximum downtime in hangar (<i>months</i>) •322 (AF) & Permit Modification for two new water tanks •Most expensive option
<p>#2B: Upgrade to High Expansion Foam system (no tanks)</p>	\$1.1M	<ul style="list-style-type: none"> •Least expensive •Permit modifications not required •No tanks required •No upgrades to pumps required 	<ul style="list-style-type: none"> •Unreliable water source. (DOE FPE Does not recommend) •AF Exception Required (higher risk) <ul style="list-style-type: none"> •ETL requirement for reduction in hose demand at 500gpm cannot be met (request 100gpm) •ETL deviation for backflow preventers location •All engineering solutions have been used to marginally provide enough flow. No wiggle room left in design to meet code. Further design may render this option N/A. •Maximum downtime in hangar (<i>months</i>)

Option 2A Chosen

- New ground-level fire tanks to provide dedicated fire water to Hangar building suppression systems
- New fire pumps, motors and controllers
- New jockey pump
- New high expansion foam system
- Convert 2 deluge pendant sprinkler systems to a single upright wet-pipe sprinkler system
- Use original fire alarm control panels and UV/IR detectors

Project Duration – 8 Months

- Project Notice to Proceed was issued 10/11/12
- System was placed in-service 4/3/2013
 - 2 Month Trial before acceptance test
- Foam System Acceptance Test was performed in June 2013

Impairment Plan

- **DOE NNSA OST B481 Fire System Impairment Plan**
 - Developed detailed impairment plan approved by KAFB Fire Department
 - Followed detailed schedule
 - Dates of Impairment: **2/4/2013 – 4/3/2013**
 - Implemented:
 - Red-Tag procedure
 - Hot Work procedure
 - Fire Watch program
 - Impaired fire hydrant map
 - Compensatory Measures
 - No Hot Work allowed in Hangar during impairment
 - UV/IR detectors remained in-service
 - Hourly fire watch and Log
 - 24x7 Security Guard On-Site

New 8-inch path from KAFB (12-inch) Water Supply



New 8-inch installation



New 8-inch Installation



New 8-inch



New 8-inch w/ thrust-block



New 8-inch buried with asphalt



Path of New 14-inch from Tanks to Pump Room



New 14-inch + Electrical to Pump Room



Covered New 14-inch to Pump Room



New 14-inch Connection to Pump Room via original PIV



Original Pump Room PIV



Excavated Pump Room PIV



14-inch Feed Main into Pump Room



New PIV to Pump Room



New Covered PIV to Pump Room



Underground Hydro-Testing



Underground Hydro-Testing



Underground Hydro-Testing



New Tank Locations



Tank Foundation Prep



Tank Foundation Prep



Tank Foundation Rebar





Tank Grounding



Tank Grounding



Tank Concrete



Tank Concrete



Tank Concrete



Tank Pads



Tank Installation



Tank Installation



Tank Installation



Tank Installation



Tank Installation



Tank Installation



Tank Installation



Tank Installation




Tank Installation



USA Tanks Installation



Tanks Bolted & Sealed



Tank 8-inch Fill Line



Tank Ladder



Finished Tanks



Trench for 8-inch Feed to Tanks



8-inch Feed to Tanks and 14-inch Feed to Pump Room



Tank Temperature Sensor



8-inch Feed Tee to Tanks



14-inch Tee from Tank to Pump Room




14-inch Feeds from Tanks to Pump Room



14-inch Suction from Tank



Tank Cathodic Protection




Tank Cathodic Protection



LPS Air Terminal Connections



Tank Grounding



Grounding Connections



Tank Grounding System Check



14-inch Suction from Tank



Altitude Valve Installation w/ Pressure Sensing Line for Tank Refill



Tank Fill



Tank Level Indicator



Tank Overflow



Completed Tanks with 8-inch Refill Line and 14-inch Suction Lines




Original Fire Pump Room



Door & Frame Removed from Pump Room



Original Discharge Piping in Pump Room




Original Sylvania Fire Pump Controller - Replaced



Original Foam Tank



Fire Alarm Control Panel in Pump Room – Not replaced



Pumps and Piping Removed



Original Low-Expansion Foam donated to KAFB Fire Department



Pumps and Piping removed




Tank Removal



Tank Removal



Revised Pump Room Layout



New Foam Tank – Chemguard C2 – 2% HE Foam



New Fire Pump




New Fire Pump and Motor



New Piping in Pump Room



New Pumps, Motors and Piping



New Foam Tank and Riser



New Master Fire Pump Controller



New Electrical Main Distribution Panel (MDP) installed to meet new fire pump demand



Original LE Deluge System Pull Station and Dead-man



New HE Foam Pull Station and Deadman and Foam System Test Header



Hangar Pipe being converted to Upright Wet-pipe



Distance from ceiling to deflector (Reqt. <12-inches)



New High Expansion Foam system piping



7 HEF Generators installed in Hangar Ceiling



Hydro-testing system piping



Multiple leaks from original deluge piping



Flushing original deluge system piping



Flushed original deluge piping at several locations



Very corroded piping



Clogged Sprinkler Tee's



Totally clogged branch-line



Totally clogged branch-line



Totally clogged branch-line



Clogged sprinkler head




Clogged sprinkler heads



Dried corrosion debris from deluge pendant sprinkler heads



Corroded Piping



Drainage Issue in Pump Room



Clogged floor drain pipe from Pump Room - replaced



Surprise - New 6-inch feed required to Hangar Vehicle Maintenance Facility B-480



New 6-inch Feed to B-480 Hangar Vehicle Maintenance Facility



Fire Pump Testing



Fire Pump Testing



Project Issues

- Configuration Management
- Fire Protection Program
- Maintenance
- Other
- Logistics – New HEF System

Configuration Management Issues

- KAFB Water Utility drawing incorrect
 - Building 480 and other buildings found being serviced from 500K Tank – potable water
 - Had to re-feed these buildings from KAFB water supplies
- No fire sprinkler drawings, calculations or design basis for OST B481 Hangar

Maintenance Issues

- 500K Tank was not being maintained – needed internal and structural inspection
- Broken altitude valve feeding 500K Tank that required Manual refilling Quarterly
- “Sub-Contracted” ITM not being performed per NFPA
- Piping not flushed as required after several accidental LE Foam system trips
- Many pinhole leaks in deluge piping
- Clogged piping and heads – System would not have operated as designed
- Existing Foam Bladder found compromised – Not testing foam concentrate
- Broken PIV – Not being exercised

Fire Protection Program Issues

- No formal fire system impairment process being implemented by OST, Contractor or Sub-Contractor
- Several times throughout the scope, design and project – foam system solenoids were found removed
 - Resulted in ORPS Report NA--OST-OST-OSTBOP-2012-0001
 - Root-Cause Analysis and Lessons Learned
- Inadequate training on fire system, operations, response and ITM

Other Issues

- AHJ not clear throughout project – Air force HQ, Local KAFB FM, Local KAFB Contractor, or NNSA
- Took 2 months to perform acceptance test and place system in-service
- Existing electrical transformer would not support both pumps running and complex service simultaneously – installed electrical shunt trip to complex
- Hard time meeting 12-inch requirement converting pendant deluge sprinklers to upright wet-pipe
- Replaced clogged floor drain in fire pump room
- Replaced broken oil/water separator in hangar
- Resurfaced hangar floor after foam acceptance testing

Logistics Issues – New HEF System

- New Inspection, Testing & Maintenance Procedures for new system
- Train occupants on new system features and operations (electrical shunt trip)
- New response protocols for occupants, security and fire department
- New system impairment process
- Other

Eglin AFB HEF Fatality Summary - 1/8/2014

- Jan 2014 Polar Vortex (Low Temp 17 deg. F) – Freezing in Gulf – Frozen sprinkler ITV that burst and tripped sprinkler flow switch – HE Foam accidental system trip
- Hangar personnel called into Maintenance leaking ITV twice before it burst
- 90,600 square foot hangar
- Foam filled hangar to 17-feet
- Four Contractors working in adjacent office building were helping fire department clear building – got curious about foam and took elevator from 3rd floor down into hangar where foam over-came elevator car against FD Direction.
 - 2nd & 3rd Contractor found a way out
 - 4th Contractor rescued after 5 minutes
 - 1st Contractor rescued after 1Hr-19Mins – fatality
- Workers were not familiar with Hangar building and hazards of foam
- They had no business entering 1st floor of hangar after told by fire department
- Training required for building occupants, system operation, response protocols, fire department rescue after actuation
- Issues with HEF system trip delay with automatic flow switch actuation
- Previous AF Spec – Wet-pipe sprinklers and HE Foam Activated: manually, flow switch OR UV/IR detectors.
- Current AF Spec – Wet-pipe sprinklers and HE Foam Activated: manually, flow switch AND UV/IR detectors

NW Camera - Hangar



SE Camera - Hangar



Foam System Acceptance Test Criteria

- Air Force ETL 98-8
 - A3.5.2. High expansion foam systems must deliver sufficient foam to cover the aircraft servicing area and adjacent accessible areas to a depth of 1 meter (3 feet) in 4 minutes or less.
 - A3.5.2.1. Concentrate and water supply must permit continuous operation of the system to generate four times the submergence volume (A3.5.2) for not less than 15 minutes. No additional foam is required for maintenance of the submergence volume beyond this 15 minutes.
 - Similar to NFPA 11 requirements.

High Expansion Foam System Trip Video



Questions????