# Technology Readiness Assessment Summaries



# Office of Technology Innovation and Development Office of Environmental Management

September 2011

# **Technology Readiness Assessment Summary**

<u>Number</u>	<u>Title</u>	Report Date
---------------	--------------	-------------

TRA-1	Waste Treatment and Immobilization Plant (WTP) Analytical Laboratory, Balance of Facilities and LAW Waste Vitrification Facilities at Hanford	March 2007
TRA-2	Waste Treatment and Immobilization Plant (WTP) HLW Waste Vitrification Facility at Hanford	March 2007
TRA-3	Waste Treatment and Immobilization Plant (WTP) Pretreatment Facility at Hanford	March 2007
TRA-4	K Basins Sludge Treatment Process at Hanford	August 2007
TRA-5	Savannah River Site Tank 48H Waste Treatment Project at SRS	July 2007

TRA-6	233Uranium Downblending and Disposition Project at Oak Ridge/ORNL	September 2008
TRA-7	SRS Salt Waste Processing Facility at SRS	July 2009
TRA-8	K Basins Sludge Treatment Project Phase 1 At Hanford Richland Operations/RL	November 2009
TRA-9	Preliminary TRA of the Calcine Disposition Project Idaho National Laboratory/INL	February 2011
TRA-10	TRA of the Small Column Ion Exchange (SCIX) Program at SRS	November 2011

EM Project: Waste Treatment Plant/WTP

TRA Report Date: March 2007

# Technology Readiness Assessn ent Summany

**United States Department of Energy Office of Environmental Management (DOE-EM)** 

# Waste Treatment and Immobilization Plant (WTP) Analytical Laboratory, Balance of Facilities and LAW Waste Vitrification Facilities

# Why DOE-EM Did Thi Review

Schematic of Laser Ablation Analytical Subsystem

DOE is constructing a Waste Treatment and Immobilization Plant (WTP) at Hanford to treat the site's tank wastes. he WTP is composed of several facilities including an Analytical La oratory (LAB), Balances of Facilities (BOF) operations, and Low-Activity Waste (LAW) Vitrification Facility. The purpose of this assessment as to identify the critical techn logy elements (CTEs) in the abovementioned facilities (LAB, BOF, and LAW) an determine if these are sufficiently mature to be incorporated into the final WTP design, which normally requires a Technology Readiness Level of

# What the TRA Team Found

The assessment team identified the following CTEs, along with each ele ent's Technology Readines Level (TRL) for the LAB, BOF and LAW facilities:

- Two LAB systems were CTEs:
  - 1. Autosampling System (T L=6), and
  - Laser ablation analysis system: LA-ICP-AES/LA-ICP-MS (TRL=5)

- No BOF systems were CTEs
- Five LAW systems were CTEs:
  - 1. LAW Melter Feed Process System (TRL=6),
  - 2. LAW Melter System (RL=6),
  - LAW Offgas and Vent systems: LOP/LVP (TRL=6),
  - 4. LAW C ntainer Sealing Subsystem (TRL=5), and
  - 5. LAW D contamination Subsystem (RL=4)

The team concluded that the CTEs are "sufficiently m ture to contin e to advance the final design."

### What the TRA Team ecommended

The assessment team recommended the following:

- Testing the LAB's Laser Ablation Atomic Emission Spectrometry subsystem using actual waste samples to demonstrate the achie able detection limits and turnar und times.
- Testing the LAW's container inert filling, flange cleaning, inspection, and lidding/delidding system in a simulated remote environment to verify the equipment performs as required.
- Integrating testing of the LAW's container
  decontamin tion and sme r testing systems in a
  simulated remote environ ent to verify t e
  equipment performs as required and can achieve
  the specified decontamination levels. This testing
  should be s pplemented with laboratory-scale
  testing to define the operational parameters for
  the CO<sub>2</sub> decontamination system.
- Identify and qualify a LAW melter bubbler design using material other than high nickel MA 758 alloy to mitigate t e risk associated with the availability of this alloy.

To view the full TRA reports, please visit this web site: http://www.em.doe.gov/Pages/ExternalTechReviews.aspx

TRA Summary: August 2011

EM Project: Waste Treatment Plant/WTP

TRA Report Date: March 2007

# Technology Readiness Assessn ent Summany

**United States Department of Energy Office of Environmental Management (DOE-EM)** 

# Waste Treatment and Immobilization Plant (WTP) HLW Waste Vitrification Facility

## Why DOE-EM Did Thi Review



HLW aste Vitrification Facility

DOE is constructing a Waste Treatment and Immobilization Plant (WTP) at Hanford to treat the site's tank wastes. he WTP is composed of several facilities including a High-Level Waste Vitrificatio Facility (HLW). The purpose of thi assessment was to ide tify the critical technology elements (CTEs) in the H W and determine if these are sufficiently mature to be incorporated into the final WTP design, whi h normally requires a echnology Readiness Level of 6.

# What the TRA Team Found

The assessment team identified the following CTEs, along with each ele ent's Technology Readines Level (TRL) for the LW facilities:

- HLW Melter Fe d Process Sy tem (TRL=6)
- HLW Melter Process System (TRL=6)
- HLW Melter Offgas Treatment Process System/Process Vessel Vent System (TRL=5)
- Pulse Jet Mixer System/Rad Liquid Waste Disposal Syste (TRL=4)

The assessment team concluded that the CTEs of the HLW Vitrification Facility are sufficiently mature to continue to advance the final design.

### What the TRA Team ecommended

The assessment team recommended the following:

 Testing the prototype HLW film cooler and film cooler cleaner to demonstrate the adequacy of the equipment in a melter equipped with bubblers

blockages in the cooler) prior to cold

understand the conditions (feed concentrations, bubbling rate, bubbler locations, etc.) that increase film cooler blockages would be useful.

 Testing and analysis of the Wet Electrostatic Precipitator (WESP) to demonstrate equipment adequacy (ESP electrode power) when processing anford waste and evaluating the corrosion resistance of the 6% molybdenum stainless steel internals of the WESP.

contacted with organics, a ids (NOx, Sox, halogens), sulfur and mercury.

 Testing the pulse jet mixers for dissipating gases, blending liquids, and susp nding solids. Specific requirements for pulse jet mixing should be established.

To view the full TRA reports, please visit this web site: http://www.em.doe.gov/Pages/ExternalTechReviews.aspx

TRA Summary: August 2011




EM Project: Waste Treatment Plant/WTP

TRA Report Date: March 2007

# Technology Readiness Assessn ent Summany

**United States Department of Energy Office of Environmental Management (DOE-EM)** 

# Waste Treatment and Immobilization Plant (WTP) Pretreatment Facility



Block Diagram of Cesium Nitric Acid Recovery

DOE is constructing a Waste Treatment and Immobilization Plant (WTP) at Hanford to treat the site's tank wastes. he WTP is composed of several facilities including a Pretreatment Facility. The purpose of this assessment was to identify the critical techn logy elements (CTEs) in the Pretreatment Facility and determine if these are sufficiently mature to be incorporated into the final WTP design.

### What the TRA Team Found

The assessment team identified the following nine CTEs, along with each element's Technology Readiness Level (T L) for the Pretreatment Facility:

- Cs Nitric Acid Recovery Process System (T L=3)
- Cs Ion Exchange Process System (TRL=5)
- aste Feed Evap Process System (TRL=4)
- Treated LAW E ap Process System (TRL=4)
- Ultrafiltration Process System (TRL=3)
- Pulse Jet Mixer System (TRL=4)
- aste Feed Receipt Process System (TRL=4)
- HLW Lag Storage (TRL=4)
- Plant Wash and Disposal System (TRL=4)

The assessment team concluded that several CTEs required maturity prior to continued design.

## What the TRA Team ecommended

The assessment team generat d an extensive list of re ommendations. The following are the "major" re ommendations;( the team also supplied 12 "s pplemental" recommendations):

- Discontinue design of the Cesium Nitric cid Recovery Process (CNP) ntil: (1) a reassessment of the design and operational requirements is completed, (2) the engineering specification is revised to reflect operational conditions, and (3) the tec nology concept is demonstrated through integrated prototy ic testing.
- Testing the CNP prior to installation in the black cell using representative feed compositions to verify the process control concept and the ability to control and monitor the composition of the nitric acid product, and to demonstrate the Cs decontamin tion factor of million and the ability to decontaminate the demister pads.
- Discontinue design of the H<sub>2</sub> venting subsystem of the Cs ion exchanger until testing is completed.
- Evaluate the adequacy of feed vessel CXP-VSL-00001 design considering the anticipated issues with precipitation of solids in the feed.
- Complete testing of the Ultrafiltration Process (UFP) system prior to final design using ctual wastes in laboratory tests and with stimulants at engineering-scale tests.
- Continue evaluation of vertical equipment arrangement for UFP filter elements.
- Establish clear, quantitative, and documented mixing requirements for all Pulse Jet Mixer (PJM) vessels in the Pretreatment as well as H W Vitrification acility.
- Complete d monstration t sting of PJMs, identify and implem nt any design changes.

To view the full TRA reports, please visit this web site: http://www.em.doe.gov/Pages/ExternalTechReviews.aspx

TRA Summary: August 2011

EM Project: K Basins Sludge Treatment

Process/STP

TRA Report Date: August 2007

# Technology Readiness Assessn ent Summany

United States Department of Energy Office of Environmental Management (DOE-EM)

# **K Basins Sludge Treatment Process**

# Why DOE-EM Did Thi Review K West Badle Greater Latine Transferred Transferred

K Basins Sludge Treatm nt Process Flow Diagram

DOE is constructing a K Basins SI dge Treatment Process (STP) for retrieving, treati g, and packa ing the various sludge streams stored in the K West Basin at Ha ford. The STP is comprised of seven major subsystems: sludge containerization, retrieval, transfer, oxidation, assay, packaging, and drum handling. The objective of the assessment was to perform a "finding-of-fact" appraisal of the project's overall technical maturity by first identifying the Critical Technolog Elements (CTEs) of the process then evaluating the Technology Readiness Level (TRL) of each element.

### What the TRA Team Found

The assessment team identified seven CTEs, each of which was further di ided into sub-elements. Th seven CTEs and the associated T Ls are listed elow:

- Material Mobilization (TRL=2)
- Material Transfer (TRL=4)
- Process Chemi try (TRL=2)
- Process Instrumentation (TRL=4)
- Assay (TRL=2)

- Mixing (TRL=2)
- Waste Package (TRL=4)

The team concluded that the critical technolo ies associated with the Sludge Treatment Process are not at the maturity level required to support Critical Decision-3 (CD-) for procurement and construction, but are more appropriately bet een CD-0 an CD-1.

### What the TRA Team ecommended

The team noted that one of the primary barriers of establishing higher TRLs relates to unknowns associated with the physical properties of the containerized and/or oxidized sludge. Because of this a representative simulant for testing and demonstration of process technologies has n t been developed.

Results of the assessment show that while the overall Critical Technology Element maturity levels may be lo , several technology sub-elements are at relatively high maturity level. This indicates t e need for (and the team recommends) a targeted maturation pl n that focuses on those technologies requiring further maturity.

To view the full TRA reports, please visit this web site: http://www.em.doe.gov/Pages/ExternalTechReviews.aspx

TRA Summary: August 2011



DOE Site: Savannah River Site/SRS

EM Project: SRS Tank 48H Waste Treatment

**Project** 


TRA Report Date: July 2007

# Technology Readiness Assessn ent Summary

United States Department of Energy Office of Environmental Management (DOE-EM)

# Savannah River Site Tank 48H Waste Treatment Project

# Why DOE-EM Did Thi Review



Wet Air Oxidation Process

Savannah River Tank 48H is a 1.3 million gal tank containing approximately 250, 000 gal of high-level liquid waste. The w ste is a salt s lution that also contains tetraphenylborate (TPB), which can release potentially flammable concentratio s of benzene vapor to the tank head space. Two pote tial treatment options have been identified for this organic-bearing tank waste: Wet Air Oxidation (WAO) and Fluidized Bed Steam Reformi g (FBSR). This assessment was conducted to aid in deciding which technology should be pursued for treating the Tank 4 H waste.

### What the TRA Team Found

The assessment team determined the Critical Technology Elements (CTEs) and the associated Technology Readiness Level (TRL) for each process, as listed below:

- et Air Oxidation Process:
  - Reactor sy tem (TRL=3)
  - Offgas Tre tment System (TRL=2)

- Fluidized Bed Steam Reforming Process:
  - Steam Reformer System (TRL=4)
  - Offgas Treatment System (TRL=4)
  - Product Handling System (TRL=3)

The team concluded that both WAO and FBSR are viable technologies for the treating the Tank 48H waste. FBSR is more advanced; however, both require technology maturity. The team noted that it would be preferred to choose one primary technology to receive the bulk of the effort and investment, while the other could be carried at a significantly lower investment and be used as a back-up to the primary.

### What the TRA Team ecommended

The team recommended the following for the WAO process:

- The reactor should undergo pilot-scale testing with simulants, laboratory-scale testing with actual wastes, and concept development to support design implement tion.
- The offgas system should undergo labor tory and bench-scale testing with a tual wastes (if practical). However, if usi g actual wast is not feasible in laboratory tests, offgas testing using tracers at commissioning should be considered.

The team recommended the following for the FBSR process:

- The Steam Reformer Subsystem requires further testing of the cyclone down comer and other components.
- Testing and development f the Product Handling System is required to demonstrate transferring material at the wt% levels anticipated for plant operations. In addition, te hnical issues have been identified with meeting acceptance criteria for the tank farm that may require wet pr duct sieving and/or waste blending.

To view the full TRA reports, please visit this web site: http://www.em.doe.gov/Pages/ExternalTechReviews.aspx

TRA Summary: August 2011

DOE Site: Oak Ridge/ORNL

EM Project: 233 Uranium Downblending

**Project** 

TRA Report Date: September 2008

# Technology Readiness Assessn ent Summary

United States Department of Energy Office of Environmental Management (DOE-EM)

# <sup>233</sup>Uranium Downblending and Disposition Project

# Why DOE-EM Did Thi Review



Product Packaging System and Interfaces

EM was directed to take ownership of a facility housed in Building 3019 at ak Ridge that was originally used to extract <sup>229</sup>Th (an isotope used in medical research) from <sup>233</sup>U. The mission, after takeover by EM, was to down lend the inventory of <sup>233</sup>U in Building 3019 to mitigate security and safety (especially criticality) concerns and prepare the material for transport and disposal. The project anticipated that the down lended material could be disposed at either WIPP or the Nevada Test Site. This assessment was conducted to coincide with the 30 design revie for the "back-end" of the downblendin process, thereby allowing observations and issues i entified by the assessment team to be included in the project techn logy maturity plans and/or design review.

# What the TRA Team Found

The assessment team identified the following Critical Technology Elements (CTEs) and the associated Technology Readiness Level (TRL):

- Analytical Laboratory (TRL=3)
- Concentration process Wiped Film Evaporator ( RL=4)
- Product Packaging (TRL=3)
- Offgas Treatment (TRL=2)

The team also identified a significant risk to the project's mission, which was centered on the uncertainty of th <sup>233</sup>U concentration in the source m terial. Downblending the <sup>233</sup>U may reduce the transuranic (TRU) content of the waste to below 100 nCi/g, which is the minimum TRU content acceptable at WIPP. Waste below this TRU level may be acceptable at the NTS, however, this facility was scheduled to clo e (year 2010) prior to the bl nding operations being completed. Thus WIPP was the only foreseeable pathway for disposition of the <sup>233</sup>U waste disposition, although the produced material may not m et acceptance criteria.

### What the TRA Team ecommended

The team made the following r commendations:

- The project (Analytical Lab) should dev lop a detailed sa pling and analysis plan to support process control, productio schedule, etc.
- The project (Analytical Lab) should dev lop a complete set of data quality objectives that identify requirements for turn-around tim s, detection limits, precision/ ccuracy derived from disposal criteria, etc.
- Test the Wi ed Film Evaporator with simulated waste to provide performance data.
- Test the integrated Produ t Packaging system with granular/powder simulants and with multiple repetitions of transfers (as ess solids build-up on surfaces); develop a "tightly specified" acceptance criteria.
- For Offgas Treatment the project needs to either demonstrate that the prop sed design will capture the fine particles evolved as daughter products from <sup>220</sup>Rn or modify the d sign (incorporating other CTEs) that ensure c pture of these.

To view the full TRA reports, please visit this web site: http://www.em.doe.gov/Pages/ExternalTechReviews.aspx

TRA Summary: August 2011



DOE Site: Savannah River/SRS **EM Project:** Salt Waste Processing


Facility/SWPF

TRA Report Date: July 2009

# Technology Readiness Assessn ent Summany

United States Department of Energy Office of Environmental Management (DOE-EM)

# **SRS Salt Waste Processing Facility**



SRS C mposite High Le el Waste Inventory

DOE Savannah River is constructi g a Salt Waste Processing Facility (SWPF) to separate and concentrate targeted radionuclides (Cs-137, Sr-90, and actinides) from High Level Waste (HLW) salt solutions in a s ries of unit operations. Sr and actinides are removed by contacting the waste solution (after feed adjustment) with a monosodium titanate (MST) solid sorbent in a batch mixer using air pulse agitators. The sorbent (containing Sr and actinides) is removed from solution by cross flow filtration. The filtered solution is passed to a solvent extraction process where Cs is separated to an aqueous (strip sol tion) effluent strea . The bulk solution (the raffinate) from the extraction process, ith targeted nuclides remov d to sufficiently low level, is disposed as Saltstone. he separated high activity streams; the MST adsorb inti-(with r and actinides) and the Cs effluent, are sent for vitrification in the Defense Waste Processing Facility (DWPF). Provisions are in place t perform a se ond Sr/actinides adsorption step if necessary. The SWPF federal project director requested this assessment to assur that the plan ed technologies are adequate and have been matured to levels consistent with Critical Decision-3 approval.

### What the TRA Team Found

The team identified ight Critical Technology Elements (CTE) of the SWPF which are listed below with a brief description. All CTEs were assigned a Technology Readiness Level of .

- Aluminum Chemistry feed solution adjustments may be required for processing, but coul result in undesirable precipitation of Al compounds.
- Air Pulse Agitator provides a well mixe suspension of MST solids in the salt waste solution.
- Cross Flow Filter retains the MST sorbent (with Sr and actinides) resulting in a ~5wt% slurry.
- Caustic-Sid Solvent Extraction (CSSX) Chemistry – selectively separates Cs from the bulk salt wa te solution and produces a sbearing aqueous stream suitable as feed for vitrification and a bulk salt waste (raffinate) suitable as feed for saltstone.
- Centrifugal ontactors provides contin ous extraction of Cs from the bulk salt waste solution.
- Extraction Solvent Recovery recovers entrained, high-valued organic solvent fr m the aqueous product streams.
- MST/Sludge Handling suspends and transports sludge to th melter.
- Process Integration evaluates how well all subsystems perform with each other and with other on-site facilities.

### What the TRA Team ecommended

The team provided the following recommendations:

- Continue study of operating limits to prevent and/or mini ize solids for ation in feed adjustment nd solvent extraction syste s.
- An integrated liquid waste systems model should evaluate the impacts on the SWPF and the entire liquid waste system of the Al in sludge being diverted fro the DWPF feed to the SWPF feed.
- Interaction and communic tion between the SWPF project and existing Integrated Salt Disposition Project should continue and e enhanced a much as possible in the fut re. Exchange of personnel between the projects should be c nsidered.

To view the full TRA reports, please visit this web site: http://www.em.doe.gov/Pages/ExternalTechReviews.aspx

TRA Summary: August 2011

Elements (CTEs), using a systematic, metric-based process and to evaluate the readiness of these technologies for insertion into a project design. Environmental Management performance cleanup closure

The objective of a Technology Readiness Assessment (TRA) is to determine the maturity of certain key technologies, identified as Critical Technology

DOE Site: Hanford Richland Operations/RL
EM Project: Sludge Treatment Project/STP

TRA Report Date: November 2009

# Technology Readiness Assessn ent Summary

United States Department of Energy Office of Environmental Management (DOE-EM)

# K Basins Sludge Treatment Project Phase 1

# Why DOE-EM Did Thi Review



XAGO HydroLance spra demonstration

The mission of the Sludge Treatment Project (STP) is to retrieve, treat, and package sludge from the K Basins of Hanford for disposal at a national repository. The sludge resulted from washing and packaging of spent nuclear fuel a d material cleaned up from the K East and K West Basin floors. The sludge is stored in the K West Basin in Engineered C ntainers (ECs) and settler tanks (STs). Phase 1 activities include: (1) retrieving sludge from the ECs and placing it in Sludge Transport Storage Containers (ST Cs), (2) decanting and filtering excess water from the sludge, and (3) transporting the sludge-loaded ST Cs to the Hanford Centr I Plateau for interim storage pending completion of future treatment and packaging capabilities (P ase 2). A additional feature of Phase 1 is the option of removing excess sludge from an STSC if overfilling occur. This assessment was conducted to support Critical Decision-1 approval for Ph se 1 of the project. In addition, the assessment team evaluated remobilization activities, which will be used in Ph se 2.

### What the TRA Team Found

The team identified three Critical Technology Elements (CTEs) that are described below. Each was assessed a Technology Readiness Level (T L) of 4.

- Xago HydroLance Tool: commercially available device (combine fluidizer and jet pump) used to retrieve sludge from the ECs in Phase 1 and from the STSCs in Phase 2.
- Overflow Recovery Tool: a direct suction lance with a mobilizing spray nozzle similar to Settler Retrieval Tool installed in the K West Ba in Settler Tanks used to rem ve excess sludge from an STSC.
- Booster/Decant Pump: a peristaltic hose pump used to transfer abrasive slurries and de ris for service sub erged in basin water.

The integrated process system was assigned a TRL of 4- because the final waste form and disposal path for th sludge (Phase 2) has yet to be determined.

### What the TRA Team ecommended

The team provided the following recommendations:

- Continue th planned test programs including the maintenanc and storage facility prototype tests and the submerged pump tests.
- Continue sludge aging studies, note the ffects of U metal oxidation and multi-year storage on sludge properties. Periodically sample STSCs while in storage. Develop a program to onitor and predict ludge property changes during storage period as necessary input for Phase 2.
- Search for new characterization methods to aid in evaluation of sludge transport.
- Continue th program for process improvements, for example flocculants, turbidity, and in- itu measurements.
- Proceed with Phase 2 process development as soon as possible.

To view the full TRA reports, please visit this web site: <a href="http://www.em.doe.gov/Pages/ExternalTechReviews.aspx">http://www.em.doe.gov/Pages/ExternalTechReviews.aspx</a>

TRA Summary: August 2011



DOE Site: Idaho National Lab/INL


EM Project: Calcine Disposition Project/CDP

TRA Report Date: February 2011

# Technology Readiness Assessn ent Summany

**United States Department of Energy Office of Environmental Management (DOE-EM)** 

# **Preliminary TRA of the Calcine Disposition Project**



Calcine HIP Treatment Process Flow Diagram

The Idaho high-level waste calcine is solid granular material designated through an amended ROD (issued Dec. 2009) to undergo treatment by a Hot Isostatic Press (HIP) process. The HIP process, possibly with additives, converts the calcine to a monolithic waste form ith durability and leach rates comparable to those of borosilicate glass. The calcine disposition

anticipates Critical Decision-1 (CD-1) approval in late 2012 authorizing the preliminary d sign phase. For CD-1 approval, it is typically recommended that the selected technology be at a Technology Readiness Level (TRL) of 4 or higher. The objective of this assessment was to identify the Critical Technology Elements (CTEs) of the HIP treatment process a d assign the TRLs that are anticipated by late 2010 in preparation for CD-1.

### What the TRA Team Found

The assessment team identified the eleven CTEs listed below along with the associated T Ls expected to be achieved prior to CD-1 (now scheduled for 2012):

- Retrieval//Pneumatic Transfer System (TRL=4)
- Batching and Mixing System (TRL=4)
- Ceramic Additive Formulation (TRL=3)

- Hot Isostatic Pressing Can Design (TRL=3)
- Hot Isostatic Pressing Can Containment (TRL=2)
- HIP Can Filling and Closure (TRL=4)
- Bakeout System (TRL=4)
- Canister loading/Closure (TRL=4)
- Remote Op ration and Maintenance (TRL=4)
- Characteriz tion: feed, admixture, produ t (TRL=4)
- Simulant Formulation (TRL=3)

The team identified several significant project risks, a ong which were the following:

- Design of the facility is being restricted to the Integrated aste Treatment Unit (IWTU) footprint for systems requiring Performance Class-3 construction; meeting this requirement a d the December 2035 completion date will be challenge.
- If additional sampling of calcine is required, designing a d constructing the facility within the IWTU footprint may be impractical.

Significant supporting documentation was not available to the assessment te m at the time of the re iew. A follow-up assessme t will be required prior to CD-1.

# What the TRA Team ecommended

- The project should ensure that all required documents e complete a d available to the review team for all future assessments.
- The project should complete discussions of waste form requirements with the EPA and EM as soon as possible.
- A full-scale mockup facility should be built and operated to achieve a TRL of 6 for CD-2.
- The project' technology maturity plan should identify all necessary development work and address achieving a TRL of 6 for all CTEs prior to CD-2.

To view the full TRA reports, please visit this web site: http://www.em.doe.gov/Pages/ExternalTechReviews.aspx

TRA Summary: August 2011

DOE Site: Savannah River Site **EM Program: Small Column Ion Exchange** 

TRA Report Date: November 2011

# Technology Readiness Assessment Summarv

United States Department of Energy Office of Environmental Management (DOE-EM)

# TRA of the Small Column Ion Exchange (SCIX) Program

# Why DOE-EM Did This Review Technology Description Truck **Environmental Management** box constitute the SCIX System deployed in tank risers

SCIX Process Flow Diagram

The SCIX system being developed for deployment at the Savannah River Site is a supplementary salt waste processing technology that, if implemented, will augment the baseline Salt Waste Processing Facility (SWPF) capability. The SCIX system, in combination with deployment of a Next Generation Solvent in the SWPF, is projected to provide nearly \$3B in cost savings due to schedule acceleration and elimination of "salt waste only" processing in the Defense Waste Processing Facility.

This TRA was unique in that the SCIX Program is a Technology Demonstration Operations Activity, and not a formal project, as defined in DOE Order 413.3A. Thus, correlation with Critical Decisions is not applicable; however, similar requirements were implemented by the SCIX Program Team.

This TRA was conducted to document the technical maturity of the SCIX system and validate the activities remaining to mature the technology to a Technology Readiness Level (TRL) 6.

### What the TRA Team Found

The TRA team identified the four CTEs listed below, along with the associated TRLs for each:

- Large Tank Monosodium Titanate Strike (TRL=5)
- Rotary Microfilters (TRL=5)
- Ion Exchange Columns using Crystalline Silicotitanate (TRL=5)
- Spent Resin Disposal (Grinder) (TRL=3)

The overal TRL is 3. Completion of the full scale design for the Grinder will result in an overall TRL 5 for the SCIX system. A full scale integrated system test is required to achieve TRL 6.

# What the TRA Team Recommended

1. At a minimum, the following few, relatively lowcost, activities (as compared to the full set of activities required to attain TRL 6) should be completed.

> The detailed vendor technology designs should be completed for all CTEs Interface designs to integrate the CTE components and other equipment into a system should be finalized.

The Preliminary Documented Safety Analysis should be completed.

The scope, cost, and schedule estimate should be completed for the technology development and testing required to attain TRL 6, and documented in a revision of the Technology Maturation Plan (TMP).

Implementing these recommendations would better position the program to facilitate a quick and cost effective implementation. Having the completed full scale design and PDSA would provide the validated documentation to immediately transition to fabrication and integrated testing.

To view the full TRA reports, please visit this web site: http://www.em.doe.gov/Pages/ExternalTechReviews.aspx

TRA Summary: November 2011

